

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

<b>APPLICATION FOR PERMIT TO DRILL</b>						<b>1. WELL NAME and NUMBER</b> NBU 922-34F4CS			
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						<b>3. FIELD OR WILDCAT</b> NATURAL BUTTES			
<b>4. TYPE OF WELL</b> Gas Well Coalbed Methane Well: NO						<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> NATURAL BUTTES			
<b>6. NAME OF OPERATOR</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.						<b>7. OPERATOR PHONE</b> 720 929-6515			
<b>8. ADDRESS OF OPERATOR</b> P.O. Box 173779, Denver, CO, 80217						<b>9. OPERATOR E-MAIL</b> julie.jacobson@anadarko.com			
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> UTU-0149077			<b>11. MINERAL OWNERSHIP</b> FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			<b>12. SURFACE OWNERSHIP</b> FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>			
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>			
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>			<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>			<b>19. SLANT</b> VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>			

20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2085 FSL 1026 FWL	NWSW	34	9.0 S	22.0 E	S
Top of Uppermost Producing Zone	2408 FNL 2151 FWL	SEnw	34	9.0 S	22.0 E	S
At Total Depth	2408 FNL 2151 FWL	SEnw	34	9.0 S	22.0 E	S

<b>21. COUNTY</b> UINTAH		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 1764		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 600	
		<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 661		<b>26. PROPOSED DEPTH</b> MD: 9195 TVD: 8973	
<b>27. ELEVATION - GROUND LEVEL</b> 4989		<b>28. BOND NUMBER</b> WYB000291		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> 43-8496	

Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Surf	11	8.625	0 - 2420	28.0	J-55 LT&C	0.2	Type V	180	1.15	15.8
							Class G	270	1.15	15.8
Prod	7.875	4.5	0 - 9195	11.6	I-80 LT&C	12.0	Premium Lite High Strength	310	3.38	12.0
							50/50 Poz	1260	1.31	14.3

**ATTACHMENTS**

**VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

<b>NAME</b> Gina Becker	<b>TITLE</b> Regulatory Analyst II	<b>PHONE</b> 720 929-6086
<b>SIGNATURE</b>	<b>DATE</b> 01/03/2013	<b>EMAIL</b> gina.becker@anadarko.com
<b>API NUMBER ASSIGNED</b> 43047535060000		
<b>APPROVAL</b>		

**Received: January 15, 2013**

**Kerr-McGee Oil & Gas Onshore. L.P.****NBU 922-34F4CS**

Surface:	2085 FSL / 1026 FWL	NWSW
BHL:	2408 FNL / 2151 FWL	SENW

Section 34 T9S R22E

Uintah County, Utah  
Mineral Lease: UTU-0149077

**ONSHORE ORDER NO. 1****DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**  
**Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,203'	
Birds Nest	1,510'	Water
Mahogany	1,965'	Water
Wasatch	4,386'	Gas
Mesaverde	6,721'	Gas
Sego	8,973'	Gas
TVD	8,973'	
TD	9,195'	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

11/27/2012

**Received: December 27, 2012**

7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 8973' TVD, approximately equals  
5,474 psi (0.61 psi/ft = actual bottomhole gradient)

---

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,523 psi (bottom hole pressure  
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

---

Per Onshore Order No. 2 - Max Anticipated Surf. Press. (MASP) = (Pore Pressure at next csg point-  
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.


10. **Other Information:**

Please refer to the attached Drilling Program.



## KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	November 27, 2012		
WELL NAME	NBU 922-34F4CS					TD	8,973'	TVD	9,195' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION		4,989'
SURFACE LOCATION	NWSW	2085 FSL	1026 FWL	Sec 34	T 9S	R 22E			
	Latitude: 39.990990		Longitude: -109.431916		NAD 83				
BTM HOLE LOCATION	SENW	2408 FNL	2151 FWL	Sec 34	T 9S	R 22E			
	Latitude: 39.993173		Longitude: -109.427902		NAD 83				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.								







## KERR-McGEE OIL & GAS ONSHORE LP

### DRILLING PROGRAM

#### CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	LTC	DQX
CONDUCTOR	14"	0-40'				3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2,420	28.00	IJ-55	LTC	2.23	1.66	5.86
						7,780	6,350	223,000
PRODUCTION	4-1/2"	0 to 5,000	11.60	I-80	DQX	1.11	1.13	3.07
						7,780	6,350	223,000
	4-1/2"	5,000 to 9,195'	11.60	I-80	LTC	1.11	1.13	5.61

#### Surface Casing:

(Burst Assumptions: TD = 12.0 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.61 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
			+ 0.25 pps flocele				
Option 1	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	1,920'	65/35 Poz + 6% Gel + 10 pps gilsonite	180	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,885'	Premium Lite II + 0.25 pps celloflake + .4% FL-52	310	35%	12.00	3.38
			+ .3% R-3 + .5 lbs/sk Kol-Seal + 6%Bentonite II +				
			1.2% Sodium Metasilicate + .05 lbs/sk Static Free				
	TAIL	5,310'	50/50 Poz/G + 10% salt + .05 lbs/sk Static Free	1,260	35%	14.30	1.31
			+ 1.2% Sodium Metasilicate + .5 % EC-1				
			+ .002 gps FP-6L + 2% Bentonite II				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

#### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

If extreme mud losses are observed OR cement doesn't reach surface on a well on the pad, a DV Tool may be used. With Cement Baskets above and Below it.

#### DRILLING ENGINEER:

Nick Spence / John Tuckwiller / Brian Cocchiere / Tyler Elliot


DATE: \_\_\_\_\_

#### DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young

DATE: \_\_\_\_\_

**T9S, R22E, S.L.B.&M.**



NOTES:

- ▲ = Section Corners Located
1. Well footages are measured at right angles to the Section Lines. G.L.O. distances are shown in feet or chains.
  2. 1 chain = 66 feet.
  3. The Bottom of hole bears N54°43'04"E 1377.65' from the Surface Position.
  4. NAD 83 Latitude & Longitude are (CORS 96)(EPOCH:2002).
  5. Bearings and Distances are based upon a Local Cartesian Grid, oriented to Geodetic North at the North 1/4 Corner of Section 8, T10S, R22E, S.L.B.&M. The Grid having a mean project height of 5300'. Lineal units used are U.S. Survey Foot.
  6. Basis of elevation is Tri-Sta "Two Water" located in Lot 4 of Section 1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202


**WELL PAD: NBU 922-34L**

**NBU 922-34F4CS**  
**WELL PLAT**

**2408' FNL, 2151' FWL (Bottom Hole)**  
**SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  OF SECTION 34, T9S, R22E,**  
**S.L.B.&M., UINTAH COUNTY, UTAH.**



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182



### SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED  
FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR  
UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE  
AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PROFESSIONAL LAND SURVEYOR  
REGISTRATION No. 6028691  
STATE OF UTAH

## TIMBERLINE

(435) 789-1365


ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 6-4-12	SURVEYED BY: A.F.	SHEET NO:  <b>1</b>  1 OF 20
DATE DRAWN: 6-15-12	DRAWN BY: T.J.R.	
SCALE: 1" = 1000'	Date Last Revised: 9-15-12 T J R	

WELL NAME	SURFACE POSITION					BOTTOM HOLE				
	NAD83		NAD27		FOOTAGES	NAD83		NAD27		FOOTAGES
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	
NBU 922-34F4CS	39°59'27.564"	109°25'54.896"	39°59'27.689"	109°25'52.437"	2085' FSL	39°59'35.421"	109°25'40.447"	39°59'35.546"	109°25'37.988"	2408' FNL
NBU 922-34K1BS	39°59'27.493"	109°25'54.986"	39°59'27.618"	109°25'52.527"	1026' FWL	39°59'32.390"	109°25'40.432"	39°59'32.515"	109°25'37.974"	2151' FWL
NBU 922-34L1CS	39°59'27.422"	109°25'55.075"	39°59'27.547"	109°25'52.616"	2078' FSL	39°59'32.390"	109°25'40.432"	39°59'32.515"	109°25'37.974"	2574' FSL
NBU 922-34K1CS	39°59'27.351"	109°25'55.164"	39°59'27.476"	109°25'52.706"	1019' FWL	39°59'27.777"	109°25'54.956"	39°59'27.901"	109°25'52.497"	2152' FWL
NBU 922-34J1BS	39°59'27.280"	109°25'55.254"	39°59'27.405"	109°25'52.795"	2071' FSL	39°59'29.110"	109°25'40.430"	39°59'29.235"	109°25'37.972"	2107' FSL
NBU 922-34J1CS	39°59'27.209"	109°25'55.343"	39°59'27.334"	109°25'52.884"	1012' FWL	39°59'1049°	109°25'427897°	39°59'1454°	109°25'427214°	2242' FSL
NBU 922-34K4BS	39°59'27.068"	109°25'55.522"	39°59'27.192"	109°25'53.063"	2057' FSL	39°59'30.806"	109°25'23.514"	39°59'30.930"	109°25'21.056"	2152' FWL
NBU 922-34J4BS	39°59'26.997"	109°25'55.612"	39°59'27.121"	109°25'53.153"	998' FWL	39°59'27.525"	109°25'23.506"	39°59'27.650"	109°25'21.048"	2414' FSL
NBU 80V	39°59'27.138"	109°25'55.433"	39°59'27.263"	109°25'52.974"	2050' FSL	39°59'27.525"	109°25'23.506"	39°59'27.650"	109°25'21.048"	1821' FEL
	39°59'27.138"	109°25'55.433"	39°59'27.263"	109°25'52.974"	2042' FSL	39°59'25.830"	109°25'40.428"	39°59'25.954"	109°25'37.969"	1910' FSL
	39°59'27.138"	109°25'55.433"	39°59'27.263"	109°25'52.974"	984' FWL	39°59'25.830"	109°25'40.428"	39°59'25.954"	109°25'37.969"	2152' FWL
	39°59'27.138"	109°25'55.433"	39°59'27.263"	109°25'52.974"		39°59'24.235"	109°25'23.510"	39°59'24.360"	109°25'21.053"	1749' FSL
	39°59'27.138"	109°25'55.433"	39°59'27.263"	109°25'52.974"		39°59'24.235"	109°25'23.510"	39°59'24.360"	109°25'21.053"	1822' FEL

# RELATIVE COORDINATES - From Surface Position to Bottom Hole

WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST
NBU 922-34F4CS	795.7'	1124.6'	NBU 922-34K1BS	496.1'	1132.8'	NBU 922-34L1CS	35.9'	9.2'	NBU 922-34K1CS	178.4'	1147.1'
NBU 922-34J1BS	357.8'	2470.9'	NBU 922-34J1CS	33.0'	2478.7'	NBU 922-34K4BS	-124.8'	1175.2'	NBU 922-34J4BS	-278.5'	2499.3'



**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202

## WELL PAD - NBU 922-34L

**WELL PAD INTERFERENCE PLAT**  
WELLS - NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UINTAH COUNTY, UTAH.



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182


## **TIMBERLINE**

ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

DATE SURVEYED: 6-4-12	SURVEYED BY: A.F.	SHEET NO:  <b>9</b>  9 OF 20
DATE DRAWN: 6-15-12	DRAWN BY: T.J.R.	
SCALE: 1" = 60'	Date Last Revised: 9-15-12 T.J.R.	





PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

WELL PAD - NBU 922-34L DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4988.6'  
FINISHED GRADE ELEVATION = 4988.5'  
CUT SLOPES = 1.5:1  
FILL SLOPES = 1.5:1  
TOTAL WELL PAD AREA = 3.88 ACRES  
TOTAL DISTURBANCE AREA = 5.48 ACRES  
SHRINKAGE FACTOR = 1.10  
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 922-34L  
WELL PAD - LOCATION LAYOUT  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

WELL PAD QUANTITIES  
TOTAL CUT FOR WELL PAD = 13,407 C.Y.  
TOTAL FILL FOR WELL PAD = 4,452 C.Y.  
TOPSOIL @ 6" DEPTH = 1,770 C.Y.  
EXCESS MATERIAL = 8,955 C.Y.

RESERVE PIT QUANTITIES  
TOTAL CUT FOR RESERVE PIT  
+/- 11,670 C.Y.  
RESERVE PIT CAPACITY (2' OF FREEBOARD)  
+/- 44,820 BARRELS

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE




HORIZONTAL 0 30' 60' 1" = 60'  
2' CONTOURS

SCALE: 1"=60' DATE: 7/10/12 SHEET NO: 10 OF 20  
REVISED: 9/19/12

TIMBERLINE ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078  
(435) 789-1365

Received: December 27, 2012



WELL PAD - NBU 922-34L (CLOSED LOOP) DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4988.6'  
FINISHED GRADE ELEVATION = 4988.5'  
CUT SLOPES = 1.5:1  
FILL SLOPES = 1.5:1  
TOTAL WELL PAD AREA = 3.88 ACRES  
TOTAL DISTURBANCE AREA = 5.48 ACRES  
SHRINKAGE FACTOR = 1.10  
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 922-34L

WELL PAD - LOCATION LAYOUT  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

WELL PAD QUANTITIES


TOTAL CUT FOR WELL PAD = 13,407 C.Y.  
TOTAL FILL FOR WELL PAD = 4,452 C.Y.  
TOPSOIL @ 6" DEPTH = 1,770 C.Y.  
EXCESS MATERIAL = 8,955 C.Y.

COMPLETIONS PIT QUANTITIES

TOTAL CUT FOR COMPLETIONS PIT  
+/- 9,340 C.Y.  
COMPLETIONS PIT CAPACITY  
(2' OF FREEBOARD)  
+/- 35,600 BARRELS

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE




SCALE: 1"=60' DATE: 9/19/12 SHEET NO:  
REVISD: 10B 10B OF 20


TIMBERLINE  
ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365





**CROSS SECTION A-A'**



**CROSS SECTION B-B'**

NOTE: CROSS SECTION B-B' DEPICTS  
MAXIMUM RESERVE PIT DEPTH.

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202

**WELL PAD - NBU 922-34L**

**WELL PAD - CROSS SECTIONS**

NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UTAH COUNTY, UTAH



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182


**TIMBERLINE**  
**ENGINEERING & LAND SURVEYING, INC.**  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

HORIZONTAL 0 50' 100' 1" = 100'  
VERTICAL 0 10' 20' 1" = 20'

Scale: 1"=100'	Date: 7/10/12	SHEET NO:
REVISED:	9/19/12	<b>11</b> 11 OF 20

**Received: December 27, 2012**



- PLEASE NOTE:
1. LOCATIONS OF PROPOSED FACILITIES AND PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.
  2. ACTUAL RECLAMATION AREA TO BE DETERMINED DURING INTERIM RECLAMATION.

WELL PAD - NBU 922-34L DESIGN SUMMARY

TOTAL DISTURBANCE AREA = 5.66 ACRES (INCLUDING EXISTING)  
RECLAMATION AREA = 4.28 ACRES  
TOTAL WELL PAD AREA AFTER RECLAMATION = 1.38 ACRES

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 922-34L

WELL PAD - RECLAMATION LAYOUT  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., Uintah County, Utah



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

TIMBERLINE  
ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE
- RECLAMATION AREA



HORIZONTAL 0 30' 60' 1" = 60'  
2' CONTOURS

SCALE: 1"=60' DATE: 7/10/12 SHEET NO:  
REVISED: 9/19/12 12 12 OF 20






PHOTO VIEW: FROM PIT CORNER E TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: SOUTHWESTERLY

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202

### WELL PAD - NBU 922-34L

LOCATION PHOTOS  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UTAH COUNTY, UTAH.



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182


### TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 6-4-12	PHOTOS TAKEN BY: A.F.	SHEET NO:  <b>13</b> 13 OF 20
DATE DRAWN: 6-15-12	DRAWN BY: T.J.R.	
Date Last Revised:		





### Legend

- Proposed Well Location
- Natural Buttes Unit Boundary
- Access Route - Proposed

Distance From Well Pad - NBU 922-34L To Unit Boundary:  $\pm 3,206$ ft

### WELL PAD - NBU 922-34L

#### TOPO A

NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UINTAH COUNTY, UTAH

### Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street  
Denver, Colorado 80202



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182



SCALE: 1:100,000

NAD83 USP Central

SHEET NO:

DRAWN: TL

DATE: 5 July 2012

**14**

REVISED:


DATE:

14 OF 20

**Received: December 27, 2012**



File: K:\ANADARKO\2012\2012\_36\_NBU\_FOCUS\_922-34\GIS\Maps\_ABCDENBU 922-34\NBU 922-34L\_B.mxd, 9/22/2012 1:56:36 PM



### Legend

- |                   |            |                     |                          |                             |           |
|-------------------|------------|---------------------|--------------------------|-----------------------------|-----------|
| ● Well - Proposed | ■ Well Pad | --- Road - Proposed | ▬ County Road            | ■ Bureau of Land Management | ■ State   |
| ● Well - Existing |            | — Road - Existing   | ⚙ Culvert/LWC - Proposed | ■ Indian Reservation        | □ Private |

Total Proposed County Road Re-Route Length: ±50ft

### WELL PAD - NBU 922-34L

#### TOPO B

NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., Uintah County, Utah

### Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street  
Denver, Colorado 80202



#### CONSULTING, LLC

2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED: TL

NAD83 USP Central

DATE: 5 July 2012

DATE: 18 Sept 2012


SHEET NO:

15

15 OF 20

Received: December 27, 2012





Well locations derived from Utah Division of Oil, Gas and Mining (UDOGM) (oilgas.ogm.utah.gov). The estimated distances from proposed bore locations to the nearest existing bore locations are based on UDOGM data.

Proposed Well	Nearest Well Bore	Footage
NBU 922-34F4CS	CIGE 25	661ft
NBU 922-34K1BS	CIGE 25	873ft
NBU 922-34L1CS	NBU 80V	74ft
NBU 922-34K1CS	NBU 922-34K	929ft
NBU 922-34J1BS	CIGE 89D	1,402ft
NBU 922-34J1CS	NBU 922-34O	1,420ft
NBU 922-34K4BS	NBU 922-34K	810ft
NBU 922-34J4BS	NBU 922-34O	1,097ft

### Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- Well - 1 Mile Radius
- ☀ Producing
- ☺ Spudded
- APD Approved
- ⊙ Preliminary Location
- ⊕ Deferred
- ✕ Cancelled
- ⊖ Temporarily Abandoned
- ☀ Active Injector
- ⊕ Location Abandoned
- ⊖ Shut-In
- ⊕ Plugged & Abandoned

### WELL PAD - NBU 922-34L

TOPO C  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., Uintah County, Utah

**Kerr-McGee Oil &  
Gas Onshore L.P.**

1099 18th Street  
Denver, Colorado 80202



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 18 Sept 2012

DATE:


SHEET NO:

**16**

16 OF 20



File: K:\ANADARKO\2012\2012\_36\_NBU\_FOCUS\_922-34\GIS\Maps\_ABCDENBU 922-34\LNBU 922-34L.D.mxd, 9/22/2012 11:59:41 AM



NBU 922-34F4CS  
NBU 922-34K1BS  
NBU 922-34L1CS  
NBU 922-34K1CS  
NBU 922-34J1BS  
NBU 922-34J1CS  
NBU 922-34K4BS  
NBU 922-34J4BS

Proposed Liquid Pipeline	Length
=====	=====
Buried 6"(Max.) (Separator to 34M Intersection)	±235ft
Buried 6"(Max.) (34M Intersection to 34F Intersection)	±400ft
Buried 6"(Max.) (34F Intersection to 34E Intersection)	±390ft
TOTAL PROPOSED BURIED LIQUID PIPELINE =	±1,025ft

Proposed Gas Pipeline	Length
=====	=====
Buried 10" (Meter House to 34M Intersection)	±235ft
Buried 10" (34M Intersection to 34F Intersection)	±400ft
Buried 12" (34F Intersection to 34E Intersection)	±390ft
TOTAL PROPOSED BURIED GAS PIPELINE =	±1,025ft

#### Legend

- Well - Proposed
- Well - Existing
- Well Pad
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

#### WELL PAD - NBU 922-34L

TOPO D  
NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil &  
Gas Onshore L.P.

1099 18th Street  
Denver, Colorado 80202



CONSULTING, LLC

2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 18 Sept 2012

DATE:

SHEET NO:

17


17 OF 20

Received: December 27, 2012









### Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- ▬ Lease Boundary
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

### WELL PAD - NBU 922-34L

#### TOPO E

NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
LOCATED IN SECTION 34, T9S, R22E,  
S.L.B.&M., UINAH COUNTY, UTAH

### Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street  
Denver, Colorado 80202



### CONSULTING, LLC

2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 18 Sept 2012

DATE:

SHEET NO:

**19**


19 OF 20




**Kerr-McGee Oil & Gas Onshore, LP  
WELL PAD – NBU 922-34L  
WELLS – NBU 922-34F4CS, NBU 922-34K1BS,  
NBU 922-34L1CS, NBU 922-34K1CS,  
NBU 922-34J1BS, NBU 922-34J1CS,  
NBU 922-34K4BS & NBU 922-34J4BS  
Section 34, T9S, R22E, S.L.B.&M.**

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly, then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45; exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 18.7 miles to a Class D County Road to the northeast. Exit left and proceed in a northeasterly direction along the Class D County Road approximately 0.1 miles to a second Class D County Road to the southeast. Exit right and proceed in a southeasterly direction along the second Class D County Road approximately 2.6 miles to a third Class D County Road to the east. Exit left and proceed in an easterly, then northeasterly, then southeasterly direction along the third Class D County Road approximately 4.7 miles to a four-way intersection. Proceed through the four-way intersection in a southeasterly direction to a fourth Class D County Road to the northeast. Proceed in a northeasterly direction along the fourth Class D County Road approximately 0.3 miles to a fifth Class D County Road to the southeast. Exit right and proceed in a southeasterly direction along the fifth Class D County Road approximately 0.1 miles to the proposed access road to the south. Follow road flags in a southerly direction approximately 50 feet to the proposed well location.


Total distance from Vernal, Utah to the proposed well location is approximately 50.0 miles in a southerly direction.



WELL DETAILS: NBU 922-34F4CS							
GL 4989 & KB 4 @ 4993.00ft (ASSUMED)							
	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	
	0.00	0.00	14526642.84	2079830.08	39.991025	-109.431233	
DESIGN TARGET DETAILS							
Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
PBHL	8973.00	794.74	1124.52	14527457.24	2080940.43	39.993207	-109.427219
- plan hits target center							
Shape							
Circle (Radius: 25.00)							



SECTION DETAILS										
	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	
	1300.00	20.00	54.75	1279.82	99.71	141.09	2.00	54.75	172.77	
	4315.82	20.00	54.75	4113.76	695.03	983.43	0.00	0.00	1204.24	
	5315.82	0.00	0.00	5093.58	794.74	1124.52	2.00	180.00	1377.01	
	9195.25	0.00	0.00	8973.00	794.74	1124.52	0.00	0.00	1377.01	PBHL_NBU 922-34F4CS
FORMATION TOP DETAILS					PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N  Geodetic System: Universal Transverse Mercator (US Survey Feet) Datum: NAD 1927 (NADCON CONUS) Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 34 T9S R22E System Datum: Mean Sea Level					
TVDPPath	MDPath	Formation								
1203.00	1218.66	GREENRIVER								
1510.00	1544.96	BIRDSNEST								
1965.00	2029.16	MAHOGANY								
4386.00	4600.85	WASATCH								
6721.00	6943.25	MESAVERDE								
8972.99	9195.24	SEGO								
CASING DETAILS										
			TVD	MD	Name	Size				
			2415.00	2508.04	8 5/8"	8.625				







# Scientific Drilling

## **US ROCKIES REGION PLANNING**

UTAH - UTM (feet), NAD27, Zone 12N

NBU 922-34L PAD

NBU 922-34F4CS

OH

Plan: PLAN #1 PRELIMINARY

## **Standard Planning Report**

15 November, 2012



<b>Database:</b>	EDM5000-RobertS-Local	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Site:</b>	NBU 922-34L PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 922-34F4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

<b>Project</b>	UTAH - UTM (feet), NAD27, Zone 12N		
<b>Map System:</b>	Universal Transverse Mercator (US Survey Feet)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Zone 12N (114 W to 108 W)		

<b>Site</b>	NBU 922-34L PAD, SECTION 34 T9S R22E			
<b>Site Position:</b>		<b>Northing:</b>	14,526,650.96 usft	<b>Latitude:</b> 39.991050
<b>From:</b>	Lat/Long	<b>Easting:</b>	2,079,771.90 usft	<b>Longitude:</b> -109.431440
<b>Position Uncertainty:</b>	0.00 ft	<b>Slot Radius:</b>	13.200 in	<b>Grid Convergence:</b> 1.01 °

Well	NBU 922-34F4CS, 2085 FSL 1026 FWL					
Well Position	+N/-S	-9.14 ft	Northing:	14,526,642.84 usft	Latitude:	39.991025
	+E/-W	58.02 ft	Easting:	2,079,830.07 usft	Longitude:	-109.431233
Position Uncertainty		0.00 ft	Wellhead Elevation:		Ground Level:	4,989.00 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2010	12/15/12	10.85	65.83	52,184

<b>Design</b>	PLAN #1 PRELIMINARY			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	54.75

<b>Plan Sections</b>										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	20.00	54.75	1,279.82	99.71	141.09	2.00	2.00	0.00	54.75	
4,315.82	20.00	54.75	4,113.76	695.03	983.43	0.00	0.00	0.00	0.00	
5,315.82	0.00	0.00	5,093.58	794.74	1,124.52	2.00	-2.00	0.00	180.00	
9,195.25	0.00	0.00	8,973.00	794.74	1,124.52	0.00	0.00	0.00	0.00	PBHL_NBU 922-34F4

<b>Database:</b>	EDM5000-RobertS-Local	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Site:</b>	NBU 922-34L PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 922-34F4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Start Build 2.00</b>									
400.00	2.00	54.75	399.98	1.01	1.43	1.75	2.00	2.00	0.00
500.00	4.00	54.75	499.84	4.03	5.70	6.98	2.00	2.00	0.00
600.00	6.00	54.75	599.45	9.06	12.82	15.69	2.00	2.00	0.00
700.00	8.00	54.75	698.70	16.09	22.77	27.88	2.00	2.00	0.00
800.00	10.00	54.75	797.47	25.12	35.54	43.52	2.00	2.00	0.00
900.00	12.00	54.75	895.62	36.13	51.12	62.60	2.00	2.00	0.00
1,000.00	14.00	54.75	993.06	49.11	69.49	85.10	2.00	2.00	0.00
1,100.00	16.00	54.75	1,089.64	64.05	90.63	110.98	2.00	2.00	0.00
1,200.00	18.00	54.75	1,185.27	80.92	114.50	140.21	2.00	2.00	0.00
1,218.66	18.37	54.75	1,203.00	84.29	119.26	146.04	2.00	2.00	0.00
<b>GREENRIVER</b>									
1,300.00	20.00	54.75	1,279.82	99.71	141.09	172.77	2.00	2.00	0.00
<b>Start 3015.82 hold at 1300.00 MD</b>									
1,400.00	20.00	54.75	1,373.78	119.45	169.02	206.97	0.00	0.00	0.00
1,500.00	20.00	54.75	1,467.75	139.19	196.95	241.17	0.00	0.00	0.00
1,544.96	20.00	54.75	1,510.00	148.07	209.51	256.55	0.00	0.00	0.00
<b>BIRDSNEST</b>									
1,600.00	20.00	54.75	1,561.72	158.93	224.88	275.37	0.00	0.00	0.00
1,700.00	20.00	54.75	1,655.69	178.67	252.81	309.58	0.00	0.00	0.00
1,800.00	20.00	54.75	1,749.66	198.41	280.74	343.78	0.00	0.00	0.00
1,900.00	20.00	54.75	1,843.63	218.15	308.67	377.98	0.00	0.00	0.00
2,000.00	20.00	54.75	1,937.60	237.89	336.60	412.18	0.00	0.00	0.00
2,029.16	20.00	54.75	1,965.00	243.65	344.75	422.15	0.00	0.00	0.00
<b>MAHOGANY</b>									
2,100.00	20.00	54.75	2,031.57	257.63	364.53	446.38	0.00	0.00	0.00
2,200.00	20.00	54.75	2,125.54	277.37	392.46	480.59	0.00	0.00	0.00
2,300.00	20.00	54.75	2,219.51	297.11	420.40	514.79	0.00	0.00	0.00
2,400.00	20.00	54.75	2,313.48	316.85	448.33	548.99	0.00	0.00	0.00
2,500.00	20.00	54.75	2,407.45	336.59	476.26	583.19	0.00	0.00	0.00
2,508.04	20.00	54.75	2,415.00	338.18	478.50	585.94	0.00	0.00	0.00
<b>8 5/8"</b>									
2,600.00	20.00	54.75	2,501.42	356.33	504.19	617.39	0.00	0.00	0.00
2,700.00	20.00	54.75	2,595.39	376.07	532.12	651.60	0.00	0.00	0.00
2,800.00	20.00	54.75	2,689.35	395.81	560.05	685.80	0.00	0.00	0.00
2,900.00	20.00	54.75	2,783.32	415.55	587.98	720.00	0.00	0.00	0.00
3,000.00	20.00	54.75	2,877.29	435.29	615.91	754.20	0.00	0.00	0.00
3,100.00	20.00	54.75	2,971.26	455.03	643.84	788.40	0.00	0.00	0.00
3,200.00	20.00	54.75	3,065.23	474.77	671.77	822.61	0.00	0.00	0.00
3,300.00	20.00	54.75	3,159.20	494.51	699.70	856.81	0.00	0.00	0.00
3,400.00	20.00	54.75	3,253.17	514.25	727.63	891.01	0.00	0.00	0.00
3,500.00	20.00	54.75	3,347.14	533.99	755.56	925.21	0.00	0.00	0.00
3,600.00	20.00	54.75	3,441.11	553.73	783.49	959.41	0.00	0.00	0.00
3,700.00	20.00	54.75	3,535.08	573.47	811.42	993.62	0.00	0.00	0.00
3,800.00	20.00	54.75	3,629.05	593.21	839.36	1,027.82	0.00	0.00	0.00
3,900.00	20.00	54.75	3,723.02	612.95	867.29	1,062.02	0.00	0.00	0.00
4,000.00	20.00	54.75	3,816.99	632.69	895.22	1,096.22	0.00	0.00	0.00
4,100.00	20.00	54.75	3,910.95	652.43	923.15	1,130.42	0.00	0.00	0.00
4,200.00	20.00	54.75	4,004.92	672.16	951.08	1,164.63	0.00	0.00	0.00

<b>Database:</b>	EDM5000-RobertS-Local	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Site:</b>	NBU 922-34L PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 922-34F4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,300.00	20.00	54.75	4,098.89	691.90	979.01	1,198.83	0.00	0.00	0.00
4,315.82	20.00	54.75	4,113.76	695.03	983.43	1,204.24	0.00	0.00	0.00
<b>Start Drop -2.00</b>									
4,400.00	18.32	54.75	4,193.27	710.97	1,005.99	1,231.86	2.00	-2.00	0.00
4,500.00	16.32	54.75	4,288.74	728.15	1,030.29	1,261.63	2.00	-2.00	0.00
4,600.00	14.32	54.75	4,385.18	743.39	1,051.86	1,288.04	2.00	-2.00	0.00
4,600.85	14.30	54.75	4,386.00	743.51	1,052.03	1,288.25	2.00	-2.00	0.00
<b>WASATCH</b>									
4,700.00	12.32	54.75	4,482.49	756.69	1,070.67	1,311.07	2.00	-2.00	0.00
4,800.00	10.32	54.75	4,580.54	768.01	1,086.70	1,330.70	2.00	-2.00	0.00
4,900.00	8.32	54.75	4,679.21	777.35	1,099.92	1,346.88	2.00	-2.00	0.00
5,000.00	6.32	54.75	4,778.39	784.70	1,110.31	1,359.62	2.00	-2.00	0.00
5,100.00	4.32	54.75	4,877.96	790.05	1,117.88	1,368.88	2.00	-2.00	0.00
5,200.00	2.32	54.75	4,977.79	793.39	1,122.61	1,374.67	2.00	-2.00	0.00
5,300.00	0.32	54.75	5,077.75	794.72	1,124.48	1,376.96	2.00	-2.00	0.00
5,315.82	0.00	0.00	5,093.58	794.74	1,124.52	1,377.01	2.00	-2.00	0.00
<b>Start 3879.42 hold at 5315.82 MD</b>									
5,400.00	0.00	0.00	5,177.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
5,500.00	0.00	0.00	5,277.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
5,600.00	0.00	0.00	5,377.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
5,700.00	0.00	0.00	5,477.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
5,800.00	0.00	0.00	5,577.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
5,900.00	0.00	0.00	5,677.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,000.00	0.00	0.00	5,777.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,100.00	0.00	0.00	5,877.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,200.00	0.00	0.00	5,977.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,300.00	0.00	0.00	6,077.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,400.00	0.00	0.00	6,177.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,500.00	0.00	0.00	6,277.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,600.00	0.00	0.00	6,377.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,700.00	0.00	0.00	6,477.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,800.00	0.00	0.00	6,577.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,900.00	0.00	0.00	6,677.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
6,943.25	0.00	0.00	6,721.00	794.74	1,124.52	1,377.01	0.00	0.00	0.00
<b>MESAVERDE</b>									
7,000.00	0.00	0.00	6,777.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,100.00	0.00	0.00	6,877.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,200.00	0.00	0.00	6,977.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,300.00	0.00	0.00	7,077.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,400.00	0.00	0.00	7,177.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,500.00	0.00	0.00	7,277.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,600.00	0.00	0.00	7,377.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,700.00	0.00	0.00	7,477.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,800.00	0.00	0.00	7,577.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
7,900.00	0.00	0.00	7,677.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,000.00	0.00	0.00	7,777.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,100.00	0.00	0.00	7,877.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,200.00	0.00	0.00	7,977.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,300.00	0.00	0.00	8,077.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,400.00	0.00	0.00	8,177.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,500.00	0.00	0.00	8,277.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,600.00	0.00	0.00	8,377.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,700.00	0.00	0.00	8,477.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00

<b>Database:</b>	EDM5000-RobertS-Local	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4989 & KB 4 @ 4993.00ft (ASSUMED)
<b>Site:</b>	NBU 922-34L PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 922-34F4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,800.00	0.00	0.00	8,577.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
8,900.00	0.00	0.00	8,677.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
9,000.00	0.00	0.00	8,777.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
9,100.00	0.00	0.00	8,877.75	794.74	1,124.52	1,377.01	0.00	0.00	0.00
9,195.24	0.00	0.00	8,972.99	794.74	1,124.52	1,377.01	0.00	0.00	0.00
<b>SEGO</b>									
9,195.25	0.00	0.00	8,973.00	794.74	1,124.52	1,377.01	0.00	0.00	0.00
<b>TD at 9195.25 - PBHL_NBU 922-34F4CS</b>									

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-34F4CS - plan hits target center - Circle (radius 25.00)	0.00	0.00	8,973.00	794.74	1,124.52	14,527,457.25	2,080,940.43	39.993207	-109.427219

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)	
2,508.04	2,415.00	8 5/8"	8.625	11.000	

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,218.66	1,199.00	GREENRIVER			
1,544.96	1,506.00	BIRDSNEST			
2,029.16	1,961.00	MAHOGANY			
4,600.85	4,382.00	WASATCH			
6,943.25	6,717.00	MESAVERDE			
9,195.24	8,968.99	SEGO		0.00	

Plan Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
300.00	300.00	0.00	0.00	Start Build 2.00
1,300.00	1,279.82	99.71	141.09	Start 3015.82 hold at 1300.00 MD
4,315.82	4,113.76	695.03	983.43	Start Drop -2.00
5,315.82	5,093.58	794.74	1,124.52	Start 3879.42 hold at 5315.82 MD
9,195.25	8,973.00	794.74	1,124.52	TD at 9195.25

## Kerr-McGee Oil & Gas Onshore. L.P.

### NBU 922-34L PAD

<u>API #</u>	<u>NBU 922-34F4CS</u>	
	Surface: 2085 FSL / 1026 FWL	NWSW
	BHL: 2408 FNL / 2151 FWL	SENW
<u>API #</u>	<u>NBU 922-34J1BS</u>	
	Surface: 2057 FSL / 998 FWL	NWSW
	BHL: 2414 FSL / 1821 FEL	NWSE
<u>API #</u>	<u>NBU 922-34J1CS</u>	
	Surface: 2050 FSL / 991 FWL	NWSW
	BHL: 2082 FSL / 1821 FEL	NWSE
<u>API #</u>	<u>NBU 922-34J4BS</u>	
	Surface: 2028 FSL / 970 FWL	NWSW
	BHL: 1749 FSL / 1822 FEL	NWSE
<u>API #</u>	<u>NBU 922-34K1BS</u>	
	Surface: 2078 FSL / 1019 FWL	NWSW
	BHL: 2574 FSL / 2152 FWL	NESW
<u>API #</u>	<u>NBU 922-34K1CS</u>	
	Surface: 2064 FSL / 1005 FWL	NWSW
	BHL: 2242 FSL / 2152 FWL	NESW
<u>API #</u>	<u>NBU 922-34K4BS</u>	
	Surface: 2035 FSL / 977 FWL	NWSW
	BHL: 1910 FSL / 2152 FWL	NESW
<u>API #</u>	<u>NBU 922-34L1CS</u>	
	Surface: 2071 FSL / 1012 FWL	NWSW
	BHL: 2107 FSL / 1021 FWL	NWSW

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on August 16-17, 2012. Present were:

- Dave Gordon, Tyler Cox, Aaron Roe and Brian Barnett - BLM;
- Jessi Brunson - USFWS;
- Bill Knapp - ICF Consulting;
- Jacob Dunham - 609 Consulting;
- Mitch Batty - Timberline Engineering & Land Surveying, Inc.; and
- Gina Becker, Charles Chase, Lindsey Frazier, Doyle Holmes, Randy Townley and Casey McKee- Kerr-McGee

**A. Existing Roads:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Please refer to Topo B for existing roads.

**B. New or Reconstructed Access Roads:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**The following segments are "on-lease"**

±50' (0.01 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077, from the edge of pad to the T-intersection in NW/4 SW/4. Please refer to Topo B.

**C. Location of Existing Wells:**

Please refer to Topo C for exiting wells.

**D. Location of Existing and/or Proposed Facilities:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

This pad will expand the existing pad for the NBU 80V, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on of pad November 20, 2012. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

**GAS GATHERING**

*Please refer to Exhibit A and Topo D2- Pad and Pipeline Detail.*

The total gas gathering pipeline distance from the meter to the tie in point is ±6,225' and the individual segments are broken up as follows:

**The following segments are "onlease", no ROW needed.**

±235' (0.04 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077, BLM surface, New 10" buried gas gathering pipeline from the meter to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.

- ±400' (0.1 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077, BLM surface, New 10" buried gas gathering pipeline from the edge of the pad to tie-in to the proposed buried 12" gas gathering pipeline at the NBU 922-34F Pad intersection . This pipeline will be used concurrently with the NBU 922-34M Pad. Please refer to Exhibit A, Line 13.
- ±1,395' (0.3 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077 and UTU-01191-A, BLM surface, New 12" buried gas gathering pipeline from the NBU 922-34F Pad pipeline intersection to tie-in to the proposed buried 16" gas gathering pipeline at the NBU 922-33H Pad intersection. This pipeline will be used concurrently with the NBU 922-34E, NBU 922-34F and NBU 922-34M Pads. Please refer to Exhibit A, Lines 12 and 11.

**The following segments require a ROW. Anadarko Uintah Midstream (AUM) will apply for an SF-299/POD under separate cover. Listed below is the gas gathering pipeline distances:**

- ±4,195' (0.8 miles) – Section 33 T9S R22E and Section 3 and 4 T10S R22E – On-lease UTU 01191-A and UTU 01191, BLM surface, New 16" buried gas gathering pipeline from the NBU 922-33H Pad pipeline intersection to the existing 16" buried gas pipeline in 1022-3 at the NBU 1022-3E Pad intersection. Please refer to Exhibit A- Line 10.

#### **LIQUID GATHERING**

*Please refer to Exhibit B and Topo D2- Pad and Pipeline Detail.*

The total liquid gathering pipeline distance from the separator to the tie in point is ±6,225' and the individual segments are broken up as follows:

**The following segments are "onlease", no ROW needed.**

- ±235' (0.04 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077, BLM surface, New 6" buried liquid gathering pipeline from the separator to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.
- ±400' (0.1 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077, BLM surface, New 6" buried liquid gathering pipeline from the edge of the pad to tie-in to the proposed buried 6" liquid gathering pipeline at the NBU 922-34F Pad intersection . This pipeline will be used concurrently with the NBU 922-34M Pad. Please refer to Exhibit B, Line 13.
- ±1,395' (0.3 miles) – Section 34 T9S R22E (NW/4 SW/4) – On-lease UTU-0149077 and UTU-01191-A, BLM surface, New 6" buried liquid gathering pipeline from the NBU 922-34F Pad pipeline intersection to tie-in to the proposed buried 6" liquid gathering pipeline at the NBU 922-33H Pad intersection. This pipeline will be used concurrently with the NBU 922-34E, NBU 922-34F and NBU 922-34M Pads. Please refer to Exhibit B, Lines 12 and 11.
- ±4,195' (0.8 miles) – Section 33 T9S R22E and Section 3 and 4 T10S R22E – On-lease UTU 01191-A and UTU 01191, BLM surface, New 6" buried liquid gathering pipeline from the NBU 922-33H Pad pipeline intersection to the existing 6" buried liquid pipeline in 1022-3 at the NBU 1022-3E Pad intersection. This pipeline will be used concurrently with the NBU 922-33F, NBU 922-33H, NBU 922-34E, NBU 922-34F, NBU 922-34M and NBU 922-33P Pads. Please refer to Exhibit B, Line 10.



**Pipeline Gathering Construction**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**The Anadarko Completions Transportation System (ACTS) information:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Please refer to Exhibit C for ACTS Lines

**E. Location and Types of Water Supply:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Water will be hauled to location over the roads marked on Maps A and B.

**F. Construction Materials:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**G. Methods for Handling Waste:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**Materials Management**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**H. Ancillary Facilities:**

No additional ancillary facilities are planned for this location.

**I. Well Site Layout:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**J. Plans for Surface Reclamation:**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**Interim Reclamation**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

### **Final Reclamation**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

### **Measures Common to Interim and Final Reclamation**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

### **Weed Control**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

### **Monitoring**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

## **K. Surface/Mineral Ownership:**

United States of America  
Bureau of Land Management  
170 South 500 East  
Vernal, UT 84078  
(435)781-4400

## **L. Other Information:**

### **Cultural and Paleontological Resources**

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

### **Resource Reports:**

A Class I literature survey was completed on September 21, 2012 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC-12-264.

A paleontological reconnaissance survey was completed on September 20, 2012 by SWCA Environmental Consultants. For additional details please refer to report SWCA-UT12-14314-178.

Biological field survey was completed on August 25, 2012 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-845.

### **Proposed Action Annual Emissions Tables:**

Please refer to the Appendix in the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

**M. Lessee's or Operators' Representative & Certification:**

Gina T. Becker  
Senior Regulatory Analyst  
Kerr-McGee Oil & Gas Onshore LP  
PO Box 173779  
Denver, CO 80217-3779  
(720) 929-6086

Tommy Thompson  
General Manager, Drilling  
Kerr-McGee Oil & Gas Onshore LP  
PO Box 173779  
Denver, CO 80217-3779  
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

  
Gina T. Becker

November 20, 2012  
Date



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

January 15, 2013

Memorandum

To: Assistant Field Office Manager Minerals,  
Vernal Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2013 Plan of Development Natural Buttes Unit  
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2013 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ WASATCH-MESA VERDE)

### NBU 921-17C PAD

43-047-53476	NBU 921-17C4CS	Sec 17 T09S R21E 0629 FNL 2001 FWL
	BHL	Sec 17 T09S R21E 1074 FNL 2155 FWL

43-047-53483	NBU 921-17F1BS	Sec 17 T09S R21E 0634 FNL 1993 FWL
	BHL	Sec 17 T09S R21E 1405 FNL 2154 FWL

### NBU 921-17D PAD

43-047-53477	NBU 921-17E4BS	Sec 17 T09S R21E 0953 FNL 0416 FWL
	BHL	Sec 17 T09S R21E 2231 FNL 0825 FWL

43-047-53478	NBU 921-17E1CS	Sec 17 T09S R21E 0959 FNL 0424 FWL
	BHL	Sec 17 T09S R21E 1901 FNL 0825 FWL

43-047-53479	NBU 921-17E1BS	Sec 17 T09S R21E 0965 FNL 0432 FWL
	BHL	Sec 17 T09S R21E 1570 FNL 0826 FWL

43-047-53480	NBU 921-17D4BS	Sec 17 T09S R21E 0982 FNL 0457 FWL
	BHL	Sec 17 T09S R21E 0909 FNL 0827 FWL

43-047-53481	NBU 921-17D1CS	Sec 17 T09S R21E 0976 FNL 0449 FWL
	BHL	Sec 17 T09S R21E 0578 FNL 0827 FWL

43-047-53482	NBU 921-17D1BS	Sec 17 T09S R21E 0970 FNL 0440 FWL
	BHL	Sec 17 T09S R21E 0148 FNL 0834 FWL

### NBU 922-34F PAD

43-047-53484	NBU 922-34G1CS	Sec 34 T09S R22E 2030 FNL 1588 FWL
	BHL	Sec 34 T09S R22E 1913 FNL 1820 FEL

43-047-53485	NBU 922-34G1BS	Sec 34 T09S R22E 2029 FNL 1578 FWL
	BHL	Sec 34 T09S R22E 1580 FNL 1820 FEL

43-047-53486	NBU 922-34F4BS	Sec 34 T09S R22E 2032 FNL 1598 FWL
	BHL	Sec 34 T09S R22E 2076 FNL 2151 FWL

Received: January 15, 2013

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-53492	NBU 922-34B1CS	Sec 34 T09S R22E 2023 FNL 1539 FWL
	BHL	Sec 34 T09S R22E 0581 FNL 1820 FEL
43-047-53493	NBU 922-34B4BS	Sec 34 T09S R22E 2024 FNL 1549 FWL
	BHL	Sec 34 T09S R22E 0914 FNL 1820 FEL
43-047-53498	NBU 922-34B4CS	Sec 34 T09S R22E 2027 FNL 1568 FWL
	BHL	Sec 34 T09S R22E 1247 FNL 1820 FEL
43-047-53500	NBU 922-34F1BS	Sec 34 T09S R22E 2021 FNL 1529 FWL
	BHL	Sec 34 T09S R22E 1412 FNL 2151 FWL
43-047-53505	NBU 922-34F1CS	Sec 34 T09S R22E 2026 FNL 1559 FWL
	BHL	Sec 34 T09S R22E 1744 FNL 2151 FWL
<b>NBU 922-34E PAD</b>		
43-047-53487	NBU 922-34C4BS	Sec 34 T09S R22E 1991 FNL 0662 FWL
	BHL	Sec 34 T09S R22E 0747 FNL 2150 FWL
43-047-53488	NBU 922-34E1CS	Sec 34 T09S R22E 2001 FNL 0663 FWL
	BHL	Sec 34 T09S R22E 1896 FNL 0825 FWL
43-047-53489	NBU 922-34E4BS	Sec 34 T09S R22E 2021 FNL 0666 FWL
	BHL	Sec 34 T09S R22E 2228 FNL 0825 FWL
43-047-53490	NBU 922-34E4CS	Sec 34 T09S R22E 2040 FNL 0670 FWL
	BHL	Sec 34 T09S R22E 2559 FNL 0825 FWL
43-047-53491	NBU 922-34L1AS	Sec 34 T09S R22E 2030 FNL 0668 FWL
	BHL	Sec 34 T09S R22E 2406 FSL 1156 FWL
<b>NBU 922-34L PAD</b>		
43-047-53497	NBU 922-34L1CS	Sec 34 T09S R22E 2071 FSL 1012 FWL
	BHL	Sec 34 T09S R22E 2107 FSL 1021 FWL
43-047-53499	NBU 922-34K4BS	Sec 34 T09S R22E 2035 FSL 0977 FWL
	BHL	Sec 34 T09S R22E 1910 FSL 2152 FWL
43-047-53501	NBU 922-34J1BS	Sec 34 T09S R22E 2057 FSL 0998 FWL
	BHL	Sec 34 T09S R22E 2414 FSL 1821 FEL
43-047-53502	NBU 922-34J4BS	Sec 34 T09S R22E 2028 FSL 0970 FWL
	BHL	Sec 34 T09S R22E 1749 FSL 1822 FEL
43-047-53503	NBU 922-34K1CS	Sec 34 T09S R22E 2064 FSL 1005 FWL
	BHL	Sec 34 T09S R22E 2242 FSL 2152 FWL
43-047-53504	NBU 922-34K1BS	Sec 34 T09S R22E 2078 FSL 1019 FWL
	BHL	Sec 34 T09S R22E 2574 FSL 2152 FWL
43-047-53506	NBU 922-34F4CS	Sec 34 T09S R22E 2085 FSL 1026 FWL
	BHL	Sec 34 T09S R22E 2408 FNL 2151 FWL
43-047-53507	NBU 922-34J1CS	Sec 34 T09S R22E 2050 FSL 0991 FWL
	BHL	Sec 34 T09S R22E 2082 FSL 1821 FEL
<b>NBU 922-34M PAD</b>		
43-047-53508	NBU 922-34J4CS	Sec 34 T09S R22E 1203 FSL 0497 FWL
	BHL	Sec 34 T09S R22E 1416 FSL 1822 FEL
43-047-53509	NBU 922-34K4CS	Sec 34 T09S R22E 1213 FSL 0499 FWL
	BHL	Sec 34 T09S R22E 1597 FSL 2094 FWL
43-047-53510	NBU 922-34L2DS	Sec 34 T09S R22E 1232 FSL 0505 FWL
	BHL	Sec 34 T09S R22E 2021 FSL 0407 FWL
43-047-53511	NBU 922-34L3DS	Sec 34 T09S R22E 1222 FSL 0502 FWL
	BHL	Sec 34 T09S R22E 1587 FSL 0428 FWL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-53512	NBU 922-34M1BS	Sec 34 T09S R22E 1194 FSL 0493 FWL
	BHL	Sec 34 T09S R22E 1054 FSL 1135 FWL
<b>NBU 922-34M4 PAD</b>		
43-047-53513	NBU 922-34M4BS	Sec 34 T09S R22E 0325 FSL 0787 FWL
	BHL	Sec 34 T09S R22E 0415 FSL 0826 FWL
43-047-53514	NBU 922-34M4CS	Sec 34 T09S R22E 0295 FSL 0747 FWL
	BHL	Sec 34 T09S R22E 0115 FSL 0716 FWL
43-047-53515	NBU 922-34N1CS	Sec 34 T09S R22E 0319 FSL 0779 FWL
	BHL	Sec 34 T09S R22E 0913 FSL 2153 FWL
43-047-53516	NBU 922-34N4BS	Sec 34 T09S R22E 0307 FSL 0763 FWL
	BHL	Sec 34 T09S R22E 0581 FSL 2153 FWL
43-047-53517	NBU 922-34N4CS	Sec 34 T09S R22E 0301 FSL 0755 FWL
	BHL	Sec 34 T09S R22E 0201 FSL 2140 FWL
43-047-53518	NBU 922-34O1BS	Sec 34 T09S R22E 0313 FSL 0771 FWL
	BHL	Sec 34 T09S R22E 1083 FSL 1822 FEL
<b>NBU 921-17G PAD</b>		
43-047-53519	NBU 921-17B4CS	Sec 17 T09S R21E 1527 FNL 2258 FEL
	BHL	Sec 17 T09S R21E 1239 FNL 1823 FEL
43-047-53520	NBU 921-17F1CS	Sec 17 T09S R21E 1529 FNL 2288 FEL
	BHL	Sec 17 T09S R21E 1736 FNL 2152 FWL
43-047-53521	NBU 921-17F4BS	Sec 17 T09S R21E 1528 FNL 2278 FEL
	BHL	Sec 17 T09S R21E 2066 FNL 2151 FWL
43-047-53523	NBU 921-17G4BS	Sec 17 T09S R21E 1528 FNL 2268 FEL
	BHL	Sec 17 T09S R21E 2106 FNL 1832 FEL
<b>NBU 921-17H PAD</b>		
43-047-53522	NBU 921-17A4BS	Sec 17 T09S R21E 2074 FNL 0557 FEL
	BHL	Sec 17 T09S R21E 0744 FNL 0496 FEL
43-047-53524	NBU 921-17A4CS	Sec 17 T09S R21E 2076 FNL 0547 FEL
	BHL	Sec 17 T09S R21E 1074 FNL 0496 FEL
43-047-53525	NBU 921-17H1BS	Sec 17 T09S R21E 2078 FNL 0538 FEL
	BHL	Sec 17 T09S R21E 1405 FNL 0496 FEL
43-047-53526	NBU 921-17H1CS	Sec 17 T09S R21E 2080 FNL 0528 FEL
	BHL	Sec 17 T09S R21E 1736 FNL 0495 FEL
43-047-53527	NBU 921-17H4CS	Sec 17 T09S R21E 2082 FNL 0518 FEL
	BHL	Sec 17 T09S R21E 2495 FNL 0489 FEL

Michael L. Coulthard

Digitally signed by Michael L. Coulthard  
 DN: cn=Michael L. Coulthard, o=Bureau of Land Management,  
 ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US  
 Date: 2013.01.15 14:15:41 -0700

bcc: File - Natural Buttes Unit  
 Division of Oil Gas and Mining  
 Central Files  
 Agr. Sec. Chron  
 Fluid Chron

MCoulthard:mc:1-15-13

**Received: January 15, 2013**



API	Well Name	Surface Location			
43-047-53476	NBU 921-17C4CS	Sec 17	T09S	R21E	0629 FNL 2001 FWL
43-047-53477	NBU 921-17E4BS	Sec 17	T09S	R21E	0953 FNL 0416 FWL
43-047-53478	NBU 921-17E1CS	Sec 17	T09S	R21E	0959 FNL 0424 FWL
43-047-53479	NBU 921-17E1BS	Sec 17	T09S	R21E	0965 FNL 0432 FWL
43-047-53480	NBU 921-17D4BS	Sec 17	T09S	R21E	0982 FNL 0457 FWL
43-047-53481	NBU 921-17D1CS	Sec 17	T09S	R21E	0976 FNL 0449 FWL
43-047-53482	NBU 921-17D1BS	Sec 17	T09S	R21E	0970 FNL 0440 FWL
43-047-53483	NBU 921-17F1BS	Sec 17	T09S	R21E	0634 FNL 1993 FWL
43-047-53484	NBU 922-34G1CS	Sec 34	T09S	R22E	2030 FNL 1588 FWL
43-047-53485	NBU 922-34G1BS	Sec 34	T09S	R22E	2029 FNL 1578 FWL
43-047-53486	NBU 922-34F4BS	Sec 34	T09S	R22E	2032 FNL 1598 FWL
43-047-53487	NBU 922-34C4BS	Sec 34	T09S	R22E	1991 FNL 0662 FWL
43-047-53488	NBU 922-34E1CS	Sec 34	T09S	R22E	2001 FNL 0663 FWL
43-047-53489	NBU 922-34E4BS	Sec 34	T09S	R22E	2021 FNL 0666 FWL
43-047-53490	NBU 922-34E4CS	Sec 34	T09S	R22E	2040 FNL 0670 FWL
43-047-53491	NBU 922-34L1AS	Sec 34	T09S	R22E	2030 FNL 0668 FWL
43-047-53492	NBU 922-34B1CS	Sec 34	T09S	R22E	2023 FNL 1539 FWL
43-047-53493	NBU 922-34B4BS	Sec 34	T09S	R22E	2024 FNL 1549 FWL
43-047-53497	NBU 922-34L1CS	Sec 34	T09S	R22E	2071 FSL 1012 FWL
43-047-53498	NBU 922-34B4CS	Sec 34	T09S	R22E	2027 FNL 1568 FWL
43-047-53499	NBU 922-34K4BS	Sec 34	T09S	R22E	2035 FSL 0977 FWL
43-047-53500	NBU 922-34F1BS	Sec 34	T09S	R22E	2021 FNL 1529 FWL
43-047-53501	NBU 922-34J1BS	Sec 34	T09S	R22E	2057 FSL 0998 FWL
43-047-53502	NBU 922-34J4BS	Sec 34	T09S	R22E	2028 FSL 0970 FWL
43-047-53503	NBU 922-34K1CS	Sec 34	T09S	R22E	2064 FSL 1005 FWL
43-047-53504	NBU 922-34K1BS	Sec 34	T09S	R22E	2078 FSL 1019 FWL
43-047-53505	NBU 922-34F1CS	Sec 34	T09S	R22E	2026 FNL 1559 FWL
43-047-53506	NBU 922-34F4CS	Sec 34	T09S	R22E	2085 FSL 1026 FWL
43-047-53507	NBU 922-34J1CS	Sec 34	T09S	R22E	2050 FSL 0991 FWL
43-047-53508	NBU 922-34J4CS	Sec 34	T09S	R22E	1203 FSL 0497 FWL
43-047-53509	NBU 922-34K4CS	Sec 34	T09S	R22E	1213 FSL 0499 FWL
43-047-53510	NBU 922-34L2DS	Sec 34	T09S	R22E	1232 FSL 0505 FWL
43-047-53511	NBU 922-34L3DS	Sec 34	T09S	R22E	1222 FSL 0502 FWL
43-047-53512	NBU 922-34M1BS	Sec 34	T09S	R22E	1194 FSL 0493 FWL
43-047-53513	NBU 922-34M4BS	Sec 34	T09S	R22E	0325 FSL 0787 FWL
43-047-53514	NBU 922-34M4CS	Sec 34	T09S	R22E	0295 FSL 0747 FWL
43-047-53515	NBU 922-34N1CS	Sec 34	T09S	R22E	0319 FSL 0779 FWL
43-047-53516	NBU 922-34N4BS	Sec 34	T09S	R22E	0307 FSL 0763 FWL
43-047-53517	NBU 922-34N4CS	Sec 34	T09S	R22E	0301 FSL 0755 FWL
43-047-53518	NBU 922-34O1BS	Sec 34	T09S	R22E	0313 FSL 0771 FWL
43-047-53519	NBU 921-17B4CS	Sec 17	T09S	R21E	1527 FNL 2258 FEL
43-047-53520	NBU 921-17F1CS	Sec 17	T09S	R21E	1529 FNL 2288 FEL
43-047-53521	NBU 921-17F4BS	Sec 17	T09S	R21E	1528 FNL 2278 FEL
43-047-53522	NBU 921-17A4BS	Sec 17	T09S	R21E	2074 FNL 0557 FEL
43-047-53523	NBU 921-17G4BS	Sec 17	T09S	R21E	1528 FNL 2268 FEL
43-047-53524	NBU 921-17A4CS	Sec 17	T09S	R21E	2076 FNL 0547 FEL



API	Well Name	Surface Location			
		Sec 17	T09S	R21E	
43-047-53525	NBU 921-17H1BS	Sec 17	T09S	R21E	2078 FNL 0538 FEL
43-047-53526	NBU 921-17H1CS	Sec 17	T09S	R21E	2080 FNL 0528 FEL
43-047-53527	NBU 921-17H4CS	Sec 17	T09S	R21E	2082 FNL 0518 FEL



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** NBU 922-34F4CS  
**API Well Number:** 43047535060000  
**Lease Number:** UTU-0149077  
**Surface Owner:** FEDERAL  
**Approval Date:** 1/30/2013

### Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas

RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

DEC 04 2012

FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

## APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU0149077
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE		7. If Unit or CA Agreement, Name and No. 891008900A
Contact: GINA T BECKER Email: GINA.BECKER@ANADARKO.COM		8. Lease Name and Well No. NBU 922-34F4CS
3a. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078	3b. Phone No. (include area code) Ph: 720-929-6086 Fx: 720-929-7086	9. API Well No. 43-047-53506
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWSW 2085FSL 1026FWL 39.990990 N Lat, 109.431916 W Lon At proposed prod. zone SENW 2408FNL 2151FWL 39.993173 N Lat, 109.427902 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 50 MILES SOUTHEAST OF VERNAL, UTAH		11. Sec., T., R., M., or Blk. and Survey or Area Sec 34 T9S R22E Mer SLB SME: BLM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1764	16. No. of Acres in Lease 600.00	12. County or Parish UINTAH
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 661	19. Proposed Depth 9195 MD 8973 TVD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 4989 GL	22. Approximate date work will start 07/01/2012	17. Spacing Unit dedicated to this well
23. Estimated duration 60-90 DAYS		

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) GINA T BECKER Ph: 720-929-6086	Date 12/04/2012
Title REGULATORY ANALYST II		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date MAY 29 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

Additional Operator Remarks (see next page)

JUN 03 2013

Electronic Submission #161654 verified by the BLM Well Information System  
For KERR MCGEE OIL & GAS ONSHORE L, sent to the Vernal DIV. OF OIL, GAS & MINING  
Committed to AFMSS for processing by JOHNETTA MAGEE on 12/14/2012 (13JM0144AE)

NOTICE OF APPROVAL

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\*

12.PPH 4/25/90E

MAY 7/12/11



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company: Kerr McGee Oil & Gas Onshore, LP  
Well No: NBU 922-34F4CS  
API No: 43-047-53506

Location: NWSW, Sec. 34, T9S, R22E  
Lease No: UTU-0149077  
Agreement: Natural Butte

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm_ut_vn_opreport@blm.gov</a>
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- Mitigation measures can be found in Appendix B, Table B-2, of the GNB ROD (BLM 2012b) under the following sections of the table:
  - Air Quality
  - Soils
  - Vegetation: *Sclerocactus wetlandicus*
  - Wildlife: Colorado River Fish
- All vehicles and equipment shall be cleaned either through power-washing, or other approved method, if the vehicles or equipment were previously operated outside the Uinta Basin, to prevent weed seed introduction.
- All disturbance areas shall be monitored for noxious weeds annually, for a minimum of three growing seasons following completion of project or until desirable vegetation is established
- Noxious and invasive weeds will be controlled throughout the area of project disturbance.
- Noxious weeds will be inventoried and reported to BLM in the annual reclamation report. Where an integrated pest management program is applicable, coordination has been undertaken with the state and local management program (if existing). A copy of the pest management plan will be submitted for each project.
- A pesticide use permit (PUP) will be obtained for the project, if applicable.
- Paleontological monitoring by a BLM permitted paleontologist is required for Well Pads 922-33A, 922-33D, 922-33E, 922-33H, and 922-33N; Access Road for 922-33E during all ground disturbing activities (BLM 2012b; BLM 2013c).
- Construction and development activities will be prohibited at the Well pads 922-34E, 922-34F, and 922-34L locations from 5/15 to 6/30 (BLM 2008a).
- Damage to livestock and livestock facilities would be reported as quickly as possible to the BLM and affected livestock operators. Operators would develop and employ prevention measures to

avoid damaging fences, gates, and cattle guards, including upgrading cattle guard gate widths and load-bearing requirements and fencing all open pits and cellars.

If partial or complete removal of a fence cannot be avoided, the fence would be braced and tied off per the BLM guidance. Where the fence is crossed by a road, the fence would be braced and a cattle guard and gate installed per BLM guidance.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- Cement for the 4.5 inch casing shall be brought up to a minimum of 200 feet above the surface casing shoe.
- A CBL shall be run from TD to TOC in the Production Casing.
- Variances shall be granted as requested in Section 9 of the Drilling Program of the SOP.
- Gamma Ray Log shall be run from TD to the Surface.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.



- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in CD (compact disc) format to the Vernal BLM Field Office. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

#### **OPERATING REQUIREMENT REMINDERS:**

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs,

core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000
<b>PHONE NUMBER:</b> 720 929-6582		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 1/30/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input checked="" type="checkbox"/> <b>APD EXTENSION</b>          OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L. P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.		
<b>NAME (PLEASE PRINT)</b> Kay E. Kelly		<b>PHONE NUMBER</b> 720 929 6582
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst
<b>DATE</b> 11/14/2013		<b>APPROVED BY:</b> <div style="text-align: center;"> <b>Approved by the Utah Division of Oil, Gas and Mining</b>   <b>Date:</b> November 18, 2013  <b>By:</b> </div>



## The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

### Request for Permit Extension Validation Well Number 43047535060000

API: 43047535060000

Well Name: NBU 922-34F4CS

Location: 2085 FSL 1026 FWL QTR NWSW SEC 34 TWNP 090S RNG 220E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 1/30/2013

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Kay E. Kelly

Date: 11/14/2013

Title: Regulatory Analyst Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000
<b>PHONE NUMBER:</b> 720 929-6514		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 1/8/2014	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Spud well 01/08/2014 @ 13:00. Drill 24" conductor hole to 40', run 14" X .250 wall conductor pipe, cement with 81 sacks ready mix. Anticipated surface spud date and surface casing cement 02/20/2014.		
<b>Accepted by the          Utah Division of          Oil, Gas and Mining          FOR RECORD ONLY          January 10, 2014</b>		
<b>NAME (PLEASE PRINT)</b> Doreen Green	<b>PHONE NUMBER</b> 435 781-9758	<b>TITLE</b> Regulatory Analyst II
<b>SIGNATURE</b> N/A	<b>DATE</b> 1/10/2014	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000
<b>10. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES		<b>COUNTY:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		<b>STATE:</b> UTAH
<b>TYPE OF SUBMISSION</b>  <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:  <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 6/24/2014	<b>TYPE OF ACTION</b>  <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Drilled to 9,208 ft. in Quarter 2 of 2014.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> June 25, 2014		
<b>NAME (PLEASE PRINT)</b> Ila Beale		<b>PHONE NUMBER</b> 720 929-6408
<b>SIGNATURE</b> N/A		<b>TITLE</b> Staff Reg. Specialist
<b>DATE</b> 6/24/2014		

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000
<b>PHONE NUMBER:</b> 720 929-6100		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/11/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Started completing the well. Well TD at 9,208 ft. Thank you.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> September 12, 2014		
<b>NAME (PLEASE PRINT)</b> Kay E. Kelly	<b>PHONE NUMBER</b> 720 929 6582	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 9/11/2014	



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000
<b>PHONE NUMBER:</b> 720 929-6100		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/17/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. THE WELL IS TD AT 9,208'. WAITING ON COMPLETION OPERATIONS TO BEGIN. THANK YOU.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> December 17, 2014		
<b>NAME (PLEASE PRINT)</b> Kay E. Kelly	<b>PHONE NUMBER</b> 720 929 6582	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/17/2014	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0149077			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-34F4CS			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2085 FSL 1026 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSW Section: 34 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047535060000			
<b>10. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>  <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:  <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/14/2015  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:	<b>TYPE OF ACTION</b>  <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE   <input type="checkbox"/> CHANGE TO PREVIOUS PLANS   <input type="checkbox"/> CHANGE WELL STATUS   <input type="checkbox"/> DEEPEN   <input type="checkbox"/> OPERATOR CHANGE   <input checked="" type="checkbox"/> PRODUCTION START OR RESUME   <input type="checkbox"/> REPERFORATE CURRENT FORMATION   <input type="checkbox"/> TUBING REPAIR   <input type="checkbox"/> WATER SHUTOFF   <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING   <input type="checkbox"/> CHANGE TUBING   <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS   <input type="checkbox"/> FRACTURE TREAT   <input type="checkbox"/> PLUG AND ABANDON   <input type="checkbox"/> RECLAMATION OF WELL SITE   <input type="checkbox"/> SIDETRACK TO REPAIR WELL   <input type="checkbox"/> VENT OR FLARE   <input type="checkbox"/> SI TA STATUS EXTENSION   <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR   <input type="checkbox"/> CHANGE WELL NAME   <input type="checkbox"/> CONVERT WELL TYPE   <input type="checkbox"/> NEW CONSTRUCTION   <input type="checkbox"/> PLUG BACK   <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION   <input type="checkbox"/> TEMPORARY ABANDON   <input type="checkbox"/> WATER DISPOSAL   <input type="checkbox"/> APD EXTENSION           OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input checked="" type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input checked="" type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text"/>			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> The NBU 922-34F4CS was placed on production 01/14/2015 after a new well completion. Producing from the MESAVERDE.					
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> January 15, 2015					
<b>NAME (PLEASE PRINT)</b> Doreen Green		<b>PHONE NUMBER</b> 435 781-9758			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst II			
<b>DATE</b> 1/15/2015					

FORM 3160-4  
( March 2012)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB NO. 1004-0137  
Expires: October 31, 2014

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other				5. Lease Serial No. UTU0149077	
b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Workover <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resrv., Other _____				6. If Indian, Allottee or Tribe Name	
2. Name of Operator KERR-MCGEE OIL AND GAS ONSHORE LP				7. Unit or CA Agreement Name and No. UTU63047A	
Contact: Doreen Green Email: Doreen.Green@anadarko.com				8. Lease Name and Well No. NBU 922-34F4CS	
3. Address P.O. Box 173779 Denver CO 82017			3a. Phone No. (include area code) 720-929-6000		9. API Well No. 43-047-53506
4. Location of Well (Report location clearly and in accordance with Federal requirements)*  At Surface NWSW 2085 FSL 1026 FWL Lat. 39.99099 Long. 109.431916 At top prod. interval reported below SENW 2414 FNL 2145 FWL At total depth SENW 2405 FNL 2153 FWL Lat. 39.9931993 Long. 109.4278936				10. Field and Pool, or Exploratory Natural Buttes	
				11. Sec., T., R., M., on Block and Survey or Area Sec 34 T 9S R 22E Mer SLB	
				12. County or Parish UINTAH	
				13. State UT	
14. Date Spudded 1/8/2014		15. Date T.D. Reached 5/12/2014		16. Date Completed <input type="checkbox"/> D&A <input checked="" type="checkbox"/> Ready to Prod. 1/14/2015	
17. Elevations (DF, RKB, RT, GL)* 5,007 RKB					
18. Total Depth: MD 9,208 TVD 8,980		19. Plug back T.D.: MD 9,153 TVD 8,926		20. Depth Bridge Plug Set: MD TVD	
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) TRIPLE COMBO, RADIAL CEMENT BOND GAMMA RAY CCL TEMP				22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)	

## 23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/ Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
24.000	14 STL	36.7	0	40		81			
11.000	8.625 J-55	28.0	18	2,526		1,200		0	
7.875	4.5 I-80	11.6	18	9,201		1,700		2129	

## 24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	8,522							

## 25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. of Holes	Perf. Status
A) MESA VERDE	6,932	9,208	7,138 To 9,110	0.410	168	Open
B)						
C)						
D)						

## 27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
7,138 - 9,110	PUMP 10,200 BBLS SLICKWATER, 42 BBLS HCL ACID (12.5%-18%), 216,288 LBS 30/50 MESH SAND

## 28. Production- Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	
1/14/2015	2/10/2015	24	→	22	2079	337			
Choke Size	Tbg. Press Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio		
18/64	1357	1606	→	22	2079	337			

## 28a. Production- Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity
			→					
Choke Size	Tbg. Press Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	
			→					

\*(See instructions and spaces for additional data on page 2)

## 28b. Production- Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	
Choke Size	Tbg. Press Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio		

## 28c. Production- Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	
Choke Size	Tbg. Press Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio		

29. Disposition of Gas (*Sold, used for fuel, vented, etc.*)

Sold 

## 30. Summary of Porous Zones (include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 31. Formation (Log) Markers:

Formation	Top	Bottom	Descriptions, Contents, Etc.	Name	Top
					Meas. Depth
				GREEN RIVER	1138
				BIRD'S NEST	1518
				MAHOGANY	2034
				WASATCH	4611
				MESA VERDE	6932

## 32. Additional remarks (include plugging procedure):

## 33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
- ☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☐ Other:

## 34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)\*

Name (please print) Doreen GreenTitle Regulatory Analyst II

Signature \_\_\_\_\_

Date 2/12/2015

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
2/21/2014	2:00 - 6:00	4.00	MIRU	01	E	P	58	WAIT ON DAYLIGHT
	6:00 - 7:00	1.00	MIRU	01	E	P	58	RIG DOWN
	7:00 - 16:00	9.00	MIRU	01	A	P	58	CONDUCT JSA WITH TRUCKS TO MOVE RIG / MOVE RIG FROM NBU 921-23K4BS TO THE NBU 922-34F4CS, WELL 1 OF 8. HOWCROFT FIELD SERVICES HAD 12 TRUCKS 3 SWAMPER 1 PUSHER/SAFETY MAN 2 PILOT CARS 1 FORKLIFT WELD ON RATATING HEAD / RIG UP FLOW LINE
	16:00 - 17:30	1.50	MIRU	01	B	P	58	CONTINUE RIGGING UP / CHANGE VALVE & SEATS IN PUMPS / CHANGE SHAKER SCREENS
	17:30 - 20:30	3.00	MIRU	01	B	P	58	SET UP PIPE RACKS / LOAD BHA / PICK UP BHA AND TAG @ 49' / AIR OUT PUMPS
	20:30 - 22:30	2.00	MIRU	01	B	P	58	PRE SPUD SAFETY MEETING
	22:30 - 23:00	0.50	MIRU	23	B	P	58	DRILL 12 1/4 SURFACE HOLE F/ 49' TO 200' , 151' @ 151 FPH WOB = 8 TO 12K ROTARY RPM = 65 MUD MOTOR RPM = 111 TOTAL = 166 PUMPING 650 GPM @ 200 SPM STAND PIPE PRESSURE ON/OFF = 800/600 TORQUE ON/OFF = 2000/740 PU = 30 / SO = 28 / ROT = 28 PEAK ON LINE ARCHER OFF
	23:00 - 0:00	1.00	DRLSUR	02	B	P	58	TRIP OUT OF HOLE
2/22/2014	0:00 - 1:00	1.00	DRLSUR	06	A	P	209	SLIP AND CUT DRILLING LINE
	1:00 - 1:30	0.50	DRLSUR	09	A	P	209	MAKE UPO 11" BIT / PICK UP DIERCTIONAL TOOLS / TRIP IN HOLE
	1:30 - 3:30	2.00	DRLSUR	06	A	P	209	DRILL 11" SURFACE HOLE F/ 200' TO 391', 191' @ 95.5' FPH WOB = 15 TO 19K ROTARY RPM = 60 / MUD MOTOR RPM = 111 / TOTAL = 171 PUMPING 533 GPM @ 174 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,560/1450 PU = 52 / SO = 45 / ROT = 49 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 22' = 11.52% 1.09' ABOVE & .35' RIGHT OF THE LINE NO HOLE ISSUES
	3:30 - 5:30	2.00	DRLSUR	02	B	P	209	CHANGE ROTATING HEAD RUBBER
	5:30 - 6:00	0.50	DRLSUR	07	C	P	400	

US ROCKIES REGION  
Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	6:00 - 12:00	6.00	DRLSUR	02	B	P	400	DRILL 11" SURFACE HOLE F/ 391' TO 1,109', 718' @ 119.7' FPH WOB = 18 TO 23K ROTARY RPM = 60 / MUD MOTOR RPM = 111 / TOTAL = 171 PUMPING 533 GPM @ 174 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,900/2000 PU = 57 / SO = 52 / ROT = 54 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 142' = 19.75% 5.04' ABOVE & 1.72 LEFT OF THE LINE NO HOLE ISSUES
	12:00 - 17:00	5.00	DRLSUR	02	B	P	1118	DRILL 11" SURFACE HOLE F/ 1,109' TO 1,517', 408' @ 81.6' FPH WOB = 18 TO 23K ROTARY RPM = 60 / MUD MOTOR RPM = 111 / TOTAL = 171 PUMPING 533 GPM @ 174 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,900/2000 PU = 76 / SO = 70 / ROT = 72 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 112' = 27.52% 2.79' ABOVE & .47' LEFT OF THE LINE NO HOLE ISSUES
	17:00 - 17:30	0.50	DRLSUR	07	A	P	1526	RIG SERVICE
	17:30 - 18:00	0.50	DRLSUR	22	L	Z	1526	***WORK ON FLOW LINE: THE FLOW LINE VIBRATED APART, WE EXTENDED THE PIECE THAT SLIDES IN THE AIR BOOT AND AIRED UP THE BOOT AND PUT A CHAIN AND BOOMER ON IT
	18:00 - 0:00	6.00	DRLSUR	02	B	P	1526	DRILL 11" SURFACE HOLE F/ 1,517' TO 1,955', 438' @ 73' FPH WOB = 18 TO 23K ROTARY RPM = 60 / MUD MOTOR RPM = 77 / TOTAL = 137 PUMPING 455 GPM @ 139 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,900/2000 PU = 85 / SO = 70 / ROT = 78 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 109' = 24.94% 3.08' ABOVE & 2.91' LEFT OF THE LINE NO HOLE ISSUES



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
2/23/2014	0:00 - 6:00	6.00	DRLSUR	02	B	P	1964	DRILL 11" SURFACE HOLE F/ 1,955' TO 2,381', 426' @ 71' FPH WOB = 18 TO 23K ROTARY RPM = 60 / MUD MOTOR RPM = 77 / TOTAL = 137 PUMPING 455 GPM @ 139 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,900/2000 PU = 90 / SO = 80 / ROT = 86 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 81' = 19.01% 4.0' ABOVE & 2.8' RIGHT OF THE LINE NO HOLE ISSUES
	6:00 - 8:00	2.00	DRLSUR	02	B	P	2390	DRILL 11" SURFACE HOLE F/ 2,381' TO 2,550', 169' @ 67.6' FPH WOB = 18 TO 23K ROTARY RPM = 60 / MUD MOTOR RPM = 77 / TOTAL = 137 PUMPING 455 GPM @ 139 SPM STAND PIPE PRESSURE ON/OFF = 900/650 TORQUE ON/OFF = 2,900/2000 PU = 90 / SO = 80 / ROT = 86 PEAK ON LINE ARCHER OFF LINE MUD WT 8.4 SLID 30' = 17.65% 1.06' ABOVE & 4.68' RIGHT OF THE LINE NO HOLE ISSUES
	8:00 - 10:30	2.50	DRLSUR	05	A	P	2559	SURVEY / CIRCULATE AND CONDITION HOLE / PUMP HEAVY MUD
	10:30 - 14:00	3.50	DRLSUR	06	D	P	2559	LAY DOWN DRILL PIPE / BHA / DIRECTIONAL TOOLS
	14:00 - 14:30	0.50	CSGSUR	12	A	P	2559	RIG DOWN CUSHION SUB / RIG UP CASING SPEAR
	14:30 - 17:00	2.50	CSGSUR	12	C	P	2559	PREJOB SAFETY WITH RIG CREW. RAN 57 JTS OF 8 5/8", 28#, J-55, LT&C CASING WITH CTE FLOAT GUIDE SHOE AND BAFFLE PLATE LOCATED 1 JOINT ABOVE THE SHOE. 5 CENTRALIZERS SPACED 10' ABOVE THE SHOE, 2ND & 3RD COLLARS, AND EVERY THIRD COLLAR TO 2,129'. LANDED CASING SHOE AT 2,517'. BAFFLE PLATE @ 2,471'.
	17:00 - 17:30	0.50	CSGSUR	05	D	P	2559	FILL PIPE / CIRCULATE

US ROCKIES REGION  
Operation Summary Report

Well: NBU 922-34F4CS RED			Spud date: 2/21/2014		
Project: UTAH-UINTAH		Site: NBU 922-34L PAD		Rig name no.: SST 57/57, CAPSTAR 310/310	
Event: DRILLING		Start date: 2/21/2014		End date: 5/14/2014	
Active datum: RKB @5,007.00usft (above Mean Sea Level)			UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	17:30 - 22:30	5.00	CSGSUR				2559	<p>PREJOB SAFETY MEETING WITH PRO PETRO CEMENTERS &amp; RIG CREW.</p> <p>TESTED LINES TO 2500 PSI</p> <p>PUMPED 147 BBLs FRESH WATER CLEARING SHOE RETURNS TO SURFACE</p> <p>MIXED AND PUMPED 20 BBL GELLED WATER FLUSH AHEAD OF CEMENT</p> <p>MIXED AND PUMPED 300 SX OF PREMIUM LEAD CEMENT WITH 2% CACL2 &amp; 1/4 LB/SX FLOCELE. 61.4 BBL OF SLURRY MIXED @ 12.0 PPG WITH YIELD OF 2.86 CF/SX.</p> <p>DROP PLUG ON FLY.</p> <p>DISPLACE CEMENT WITH 154.2 BBL FRESH WATER. RETURNS THROUGH OUT DISPLACEMENT. FINAL LIFT OF 250 PSI @ 3 BBL/MINUTE.</p> <p>BUMP PLUG WITH 350 PSI. HELD 650 PSI FOR 5 MINUTES.</p> <p>CHECK FLOAT. FLOAT HELD.</p> <p>TOP JOB # 1: PUMP CEMENT DOWN 1" PIPE WITH 150 SX PREMIUM CEMENT WITH 4% CACL2, 2% GR-3, &amp; 1/4 LB/SX FLOCELE. 30.7 BBL OF SLURRY MIXED @ 15.8 PPG WITH YIELD OF 1.15 CF/SX.</p> <p>WAIT ON CEMENT 2 HRS</p> <p>TOP JOB # 2: PUMP CEMENT DOWN 1" PIPE WITH 125 SX PREMIUM CEMENT WITH 4% CACL2, 2% GR-3, &amp; 1/4 LB/SX FLOCELE. 25.6 BBL OF SLURRY MIXED @ 15.8 PPG WITH YIELD OF 1.15 CF/SX</p> <p>RELEASE RIG 02/23/2014 @ 10:30</p> <p>RELEASE CEMENTERS</p>
5/7/2014	14:00 - 0:00	10.00	MIRU3	01	E	P	2559	<p>RIG DOWN -</p> <p>RIG DOWN TOP DRIVE, RIG FLOOR, 4" MUD LINES, FLOW LINE, FLAIR LINE'S, MUD TANKS, MUD PUMPS, ELECTRICAL -</p> <p>HAD 1 BED TRUCK, 1 POLE TRUCK, 1 FORKLIFT AND 1 HAUL TRUCK TO START HAULING PIPE TUBS &amp; 400 BBL UPRIGHTS</p> <p>HAUL CAMPS AND MISCELLANEOUS EQUIPMENT LOWER TOP DRIVE @ 16 HRS</p> <p>LOWER DERRICK @ 1800 HRS</p> <p>TRANSFER MUD TO LOCATION</p>
5/8/2014	0:00 - 6:00	6.00	MIRU3	01	E	P	2559	FINISH RIGGING DOWN RIG FLOOR & BACKYARD ELECTRICAL LINES - HAUL MUD TO NEW LOCATION
	6:00 - 20:00	14.00	MIRU3	01	A	P	2559	<p>MOVE RIG WITH JD FIELD SERVICES - HAD 5 HAUL TRUCKS, 1 POLE TRUCK, 2 BED TRUCKS, 2 FORKLIFTS, 2 PUSHERS &amp; 2 SWAMPERS - J&amp;C CRANE WITH RIGGER - SET OUT BACK YARD AND SPLIT SUB</p> <p>SET IN BACK YARD &amp; PUT SUB TOGETHER - SET DRAWWORKS &amp; DERRICK ON RIG FLOOR</p> <p>CRANE RELEASED @ 1900 HRS - TRUCKS RELEASED @ 2000 HRS</p>

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	20:00 - 0:00	4.00	MIRU3	01	B	P	2559	RIG UP ELECTRICAL LINES, MUD LINES, & FLARE LINES - FILL MUD TANKS
5/9/2014	0:00 - 9:30	9.50	MIRU3	01	B	P	2559	RIG UP BACKYARD - FILL MUD TANKS - SLIP ON DRILLING LINE - RAISE DERRICK @ 0600 HRS - INSTALL TOP DRIVE @ 0930 TRUCK FOR TOP DRIVE 1 HR LATE
	9:30 - 11:30	2.00	PRSPD	14	A	P	2559	NIPPLE UP BOP'S - CHOKE & KILL LINES / ROTATING HEAD & FLOW LINE
	11:30 - 15:00	3.50	PRSPD	15	A	P	2559	HOLD SAFETY MEETING, RUN TEST ASSY, TEST BOP WITH A-1 TESTERS - TEST ANNULAR TO 250 PSI LOW/ 5 MIN 2500 PSI HIGH 10 MIN, PIPE & BLIND RAMS, FLOOR VALVES, IBOP, HCR VALVE, KILL LINE VALVES, TEST BOP'S, CHOKE MANIFOLD TO 250 PSI LOW/ 5 MIN - 5000 PSI HIGH 10 MIN, HOLD ACCUMULATOR FUNCTION TEST, TEST CSG 1500 PSI - 30 MIN, RIG DOWN
	15:00 - 15:30	0.50	PRSPD	14	B	P	2559	INSTALL WEAR BUSHING
	15:30 - 16:30	1.00	PRSPD	06	J	P	2559	PICK UP SCIENTIFIC 6 1/2", 1.5 BEND, HR, 7/8 LOBE, 3.3 STAGE 0.16 RPG MUD MOTOR, ( SER #6494-114) - MAKE UP SECURITY MM65M PDC BIT, DRESSED WITH 6 X 16 JETS, (TFA = 1.178), SER #12232818 - INSTALL MWD TOOL, ORIENT & SCRIBE
	16:30 - 20:30	4.00	PRSPD	06	A	P	2559	PICK UP DRILL PIPE & TRIP IN HOLE TO TOC AT 2410' / INSTALL ROTATING RUBBER
	20:30 - 21:30	1.00	DRLPRC	02	F	P	2559	DRILL CEMENT & FLOAT EQUIPMENT, CLEAN OUT TO 2559'
	21:30 - 0:00	2.50	DRLPRC	02	D	P	2559	DIR DRILL FROM 2559' TO 2930' = 371' = 148.4 FPH 18-22K ON BIT 120 SPM = 590 GPM - MOTOR = 135 RPM 50-70 RPM ON TOP DRIVE 4-9K FT/LBS TORQUE 1650 PSI ON BTM - 1250 PSI OFF BTM P/U = 100K - SO = 75K - ROT = 85K HOLE IN GOOD SHAPE SLIDE 22% OF TIME & 27% OF FOOTAGE BOS DEWATERING - RUNNING CENTRIFUGE - RUNNING MUD CLEANER - RUNNING MUD WT = 8.4 - VIS = 26

**US ROCKIES REGION**

**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
5/10/2014	0:00 - 8:00	8.00	DRLPRV	02	B	P	2930	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 2930' TO / 3,805' = 875' @ 109.4' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 6-12K STAND PIPE PRESSURE ON BOTTOM = 1750 STAND PIPE PRESSURE OFF BOTTOM = 1,300 STRING WEIGHT UP/DOWN/ROTATING = 125K / 85K / 105K DRAG = 20K HOLE IN GOOD CONDITION SLIDE 33% OF TIME AND 29% OF FOOTAGE CURRENTLY 2.67' NORTH & 8.78' WEST OF PLAN LINE BOS DE-WATERING - RUNNING CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 SECONDS DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB
	8:00 - 15:30	7.50	DRLPRV	02	B	P	3805	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 3805' TO / 4533' = 728' @ 97.1' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 8-14K STAND PIPE PRESSURE ON BOTTOM = 1750 STAND PIPE PRESSURE OFF BOTTOM = 1,300 STRING WEIGHT UP/DOWN/ROTATING = 155K / 90K / 120K DRAG = 35K HOLE IN GOOD CONDITION SLIDE 66% OF TIME & 53% OF FOOTAGE CURRENTLY 25' SOUTH & 7.3' WEST OF PLAN LINE BOS DE-WATERING - RUNNING CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB
	15:30 - 16:00	0.50	DRLPRV	07	A	P	4533	LUBRICATE RIG

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	16:00 - 0:00	8.00	DRLPRV	02	B	P	4533	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 4533' TO / 5482' = 949' @ 118.6' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 8-14K STAND PIPE PRESSURE ON BOTTOM = 1750 STAND PIPE PRESSURE OFF BOTTOM = 1,300 STRING WEIGHT UP/DOWN/ROTATING = 180K / 95K / 130K DRAG = 50K HOLE IN GOOD CONDITION SLIDE 43% OF TIME & 35% OF FOOTAGE CURRENTLY 6.21' NORTH & 6.83' WEST OF PLAN LINE BOS DE-WATERING - RUNNING CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB
5/11/2014	0:00 - 8:00	8.00	DRLPRV	02	B	P	5482	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 5482' TO / 6350' = 868' @ 108.5' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 9-16K STAND PIPE PRESSURE ON BOTTOM = 1900 STAND PIPE PRESSURE OFF BOTTOM = 1600 STRING WEIGHT UP/DOWN/ROTATING = 200K / 100K / 135K DRAG = 50K HOLE IN GOOD CONDITION SLIDE 6% OF TIME & 3% OF FOOTAGE BOS DE-WATERING - RUNNING CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	8:00 - 16:00	8.00	DRLPRV	02	B	P	6350	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 6350' TO / 7001' = 651' @ 81.4' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 9-16K STAND PIPE PRESSURE ON BOTTOM = 1950 STAND PIPE PRESSURE OFF BOTTOM = 1650 STRING WEIGHT UP/DOWN/ROTATING = 230K / 115K / 145K DRAG = 85K HOLE IN GOOD CONDITION SLIDE 23% OF TIME & 18% OF FOOTAGE BOS DE-WATERING - OFF CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB
	16:00 - 16:30	0.50	DRLPRV	07	A	P	7001	LUBRICATE RIG
	16:30 - 0:00	7.50	DRLPRV	02	B	P	7001	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 7001' TO / 7711' = 710' @ 94.7' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 9-16K STAND PIPE PRESSURE ON BOTTOM = 2000 STAND PIPE PRESSURE OFF BOTTOM = 1650 STRING WEIGHT UP/DOWN/ROTATING = 240K / 115K / 148K DRAG = 85K HOLE IN GOOD CONDITION SLIDE 7% OF TIME & 3% OF FOOTAGE CURRENTLY 6.75' NORTH & 5.26' WEST OF PLAN BOS DE-WATERING - RUNNING CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 8.5 PPG VISCOSITY = 27 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
5/12/2014	0:00 - 8:00	8.00	DRLPRV	02	B	P	7711	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 7711' TO / 8404' = 693' @ 86.6' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 2 PUMP @ 60/60 GALLONS PER MINUTE = 590 MUD MOTOR RPM = 85, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 12-20K STAND PIPE PRESSURE ON BOTTOM = 2300 STAND PIPE PRESSURE OFF BOTTOM = 1950 STRING WEIGHT UP/DOWN/ROTATING = 260K / 115K / 150K DRAG = 110K HOLE IN GOOD CONDITION SLIDE 16% OF TIME & 6% OF FOOTAGE BOS DE-WATERING - OFF CENTRIFUGE - RUNNING DE-SANDER - RUNNING MUD WEIGHT = 9.1 PPG VISCOSITY = 32 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB 10-15' FLARE ON CONNECTIONS
	8:00 - 12:00	4.00	DRLPRV	02	B	P	8404	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 8404' TO / 8684' = 280' @ 70' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 1 PUMP @ 105 STKS - GALLONS PER MINUTE = 515 MUD MOTOR RPM = 72, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 12-21K STAND PIPE PRESSURE ON BOTTOM = 1850 STAND PIPE PRESSURE OFF BOTTOM = 1600 STRING WEIGHT UP/DOWN/ROTATING = 260K / 115K / 150K DRAG = 110K HOLE IN GOOD CONDITION SLIDE 7% OF TIME & 3% OF FOOTAGE CURRENTLY 6.75' NORTH & 5.26' WEST OF PLAN BOS DE-WATERING - OFF CENTRIFUGE - OFF DE-SANDER - RUNNING MUD WEIGHT = 9.1 PPG VISCOSITY = 32 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB START TRANSFERING HEAVY MUD @ 8650' TOOK GAS KICK WHILE TRANSFERING MUD - HAD 10-15' FLARE PRIOR TO KICK - 30-50' FLARE WHILE TRYING TO CIRCULATE GAS OUT
	12:00 - 13:00	1.00	DRLPRV	05	B	X	8684	***CIRCULATE OUT GAS KICK PUMPING 11.3# MUD DOWN HOLE - HAD 30-50' STRONG FLARE WHILE CIRCULATING KICK OUT - ABLE TO GO BACK TO DRILLING ONC 11# MUD CAME BACK TO SHAKER



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014

End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	13:00 - 15:00	2.00	DRLPRV	02	B	P	8684	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 8684' TO / 8806' = 122' @ 61' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 1 PUMP @ 105 STKS - GALLONS PER MINUTE = 515 MUD MOTOR RPM = 72, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 12-21K STAND PIPE PRESSURE ON BOTTOM = 2400 STAND PIPE PRESSURE OFF BOTTOM = 2100 STRING WEIGHT UP/DOWN/ROTATING = 280K / 135K / 176K DRAG = 104K HOLE IN GOOD CONDITION SLIDE 7% OF TIME & 3% OF FOOTAGE BOS DE-WATERING - OFF CENTRIFUGE - OFF DE-SANDER - RUNNING MUD WEIGHT = 11.6 PPG VISCOSITY = 37 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB 5-15' FLARE WHILE DRILLING
	15:00 - 15:30	0.50	DRLPRV	07	A	P	8806	LUBRICATE RIG
	15:30 - 22:30	7.00	DRLPRV	02	B	P	8806	DIRECTIONAL DRILL 7 7/8 PRODUCTION HOLE FROM / 8806' TO / 9208' = 402' @ 61' PER HOUR WEIGHT ON BIT = 18-24K STROKES PER MINUTE 1 PUMP @ 105 STKS - GALLONS PER MINUTE = 515 MUD MOTOR RPM = 72, TOP DRIVE RPM = 50-70, TOTAL RPM = 123-143 FT/LBS TORQUE = 12-21K STAND PIPE PRESSURE ON BOTTOM = 2700 STAND PIPE PRESSURE OFF BOTTOM = 2400 STRING WEIGHT UP/DOWN/ROTATING = 280K / 140K / 180K DRAG = 100K HOLE IN GOOD CONDITION CURRENTLY 9.86' NORTH & 2.5' EAST OF PLAN BOS DE-WATERING - OFF CENTRIFUGE - OFF DE-SANDER - RUNNING MUD WEIGHT = 12.2 PPG VISCOSITY = 38 DRILLING WITH FLOWZAN MUD SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB
	22:30 - 0:00	1.50	DRLPRV	05	A	P	9208	CONDITION MUD & CIRCULATE - PUMP HIGH VIS LCM SWEEP AROUND - PREPARE FOR SHORT TRIP
5/13/2014	0:00 - 1:30	1.50	DRLPRV	06	E	P	9208	WIPER TRIP 10 STANDS OUT OF HOLE - BACK REAM OUT 8 STDS OF - TRIP IN HOLE
	1:30 - 3:00	1.50	DRLPRV	05	A	P	9208	CONDITION MUD & CIRCULATE - PUMP HIGH VIS LCM SWEEP - BUILD PILL - HAD 10-15' FLARE ON BTMS UP

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: SST 57/57, CAPSTAR 310/310

Event: DRILLING

Start date: 2/21/2014



End date: 5/14/2014

Active datum: RKB @5,007.00usft (above Mean Sea Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	3:00 - 8:30	5.50	DRLPRV	06	A	P	9208	TRIP OUT OF HOLE TO RUN WEATHERFORD SHUTTLE LOGS - BACK REAM OUT 8 STDS OF PIPE - PUMP PILL & BLOW DOWN TOP DRIVE - STRAIGHT PULL @ 280K - TIGHT FROM 4600' TO 3985' - BACK REAM THROUGH - PULL OUT OF HOLE - LAY DOWN MWD TOOLS & MUD MOTOR
	8:30 - 11:30	3.00	EVALPR	06	J	P	9208	HOLD SAFETY MEETING WITH WEATHERFORD AND RIG CREW - PICK UP SHUTTLE LOGGING TOOLS & PRESSURE TEST
	11:30 - 15:30	4.00	EVALPR	06	B	P	9208	TRIP IN HOLE - BREAK CIRCULATION @ 2400', 5260' & 8000' - HOLE IN GOOD SHAPE
	15:30 - 16:00	0.50	EVALPR	07	A	P	9208	LUBRICATE RIG
	16:00 - 18:00	2.00	EVALPR	05	A	P	9208	PUMP DOWN DART TO DEPLOY LOGGING TOOL - CONDITION MUD & CIRCULATE GAS OUT - PUMP LCM SWEEP AROUND - BUILD PILL 10-15' FLARE ON BOTTOMS UP
	18:00 - 0:00	6.00	EVALPR	06	B	P	9208	PUMP PILL - BLOW DOWN TOP DRIVE - TRIP OUT OF HOLE WHILE LOGGING @ 30'/HR TO CASING SHOE - HOLE IN GOOD SHAPE
5/14/2014	0:00 - 2:00	2.00	EVALPR	06	J	P	9208	LAY DOWN ALL SHUTTLE LOGGING TOOLS
	2:00 - 2:30	0.50	EVALPR	14	B	P	9208	PULL WEAR BUSHING
	2:30 - 3:30	1.00	CSGPRO	12	A	P	9208	HOLD SAFETY MEETING / RIG UP WYOMING CASING SERVICE CASING EQUIPMENT
	3:30 - 10:00	6.50	CSGPRO	12	C	P	9208	RAN 94 JTS + 1 MARKER JTS 4 1/2", 11.6#, 180, LT&C CASING + 113 JTS + CROSSOVER + PUP JT, 4 1/2", 11.6#, 180/ DQX CASING, SHOE AT 9200.61', TOP FLOAT COLLAR AT 9153.36', RAN 15 CENT'S - TOP OF MESEVERDE MK JT 6921.51'
	10:00 - 11:30	1.50	CSGPRO	05	D	P	9208	CIRCULATE / RIG DOWN WYOMING CASING SERVICE CASING TOOLS / RIG UP BAKER CEMENTING EQUIPMENT - CIRCULATE @ 100 SPM = 490 GPM @ 1050 PSI HAD 10-15' FLARE ON BTMS UP
	11:30 - 14:30	3.00	CSGPRO	12	E	P	9208	CEMENT W/ BAKER - HOLD SAFETY MEETING - TEST LINES TO 5850 PSI - PUMP 25 BBLS WATER SPACER - 188.4 BBLS LEAD CEMENT 615 SKS @ 13 PPG W/ 1.72 YIELD, MIX & PUMP 260 BBLS TAIL CEMENT 1085 SKS @ 14.3 PPG W/ 1.34 YIELD - WASH UP LINES - DISPLACE W/ 142.3 BBLS WATER - BUMP PLUG TO 3400 PSI - HAD 2790 PSI LIFT PRESSURE PRIOR TO BUMP PLUG / GOOD RETURNS THROUGHOUT JOB - 50 BBLS WATER CEMENT TO SURFACE - RIG DOWN CEMENTERS PUMPED 25% EXCESS OF HOLE VOLUME ON LEAD & TAIL CEMENT EST TOP OF LEAD TO SURFACE EST TOP OF TAIL IS 4114'
	14:30 - 15:30	1.00	CSGPRO	12	B	P	9208	BACK OUT LANDING JT - INSTALL PACK OFF WITH CAMERON HAND - LAY DOWN LANDING JT
	15:30 - 16:30	1.00	RDMO	14	A	P	9208	NIPPLE DOWN BOP - CLEAN MUD TANKS - RELEASE RIG @ 1630 HRS ON 5/14/2014

WELL DETAILS: NBU 922-34F4CS					
GL 4989 & KB 18 @ 5007.00ft (SST 57)					
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14526642.84	2079830.08	39.9910250	-109.4312330



PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N
Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: Zone 12N (114 W to 108 W)
Location: SECTION 34 T9S R22E
System Datum: Mean Sea Level



# **US ROCKIES REGION PLANNING**

**UTAH - UTM (feet), NAD27, Zone 12N**

**NBU 922-34L PAD**

**NBU 922-34F4CS**

**OH**

**Design: OH**

## **Standard Survey Report**

**19 May, 2014**







## Survey Report



<b>Company:</b>	US ROCKIES REGION PLANNING	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>TVD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Site:</b>	NBU 922-34L PAD	<b>MD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Well:</b>	NBU 922-34F4CS	<b>North Reference:</b>	True
<b>Wellbore:</b>	OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Denver Sales

<b>Project</b>	UTAH - UTM (feet), NAD27, Zone 12N		
<b>Map System:</b>	Universal Transverse Mercator (US Survey Feet)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Zone 12N (114 W to 108 W)		

Site						NBU 922-34L PAD, SECTION 34 T9S R22E											
Site Position:			Northing:			14,526,606.18 usft			Latitude:			39.9909260					
From:			Lat/Long			Easting:			2,079,795.97 usft			Longitude:			-109.4313570		
Position Uncertainty:			0.00 ft			Slot Radius:			13.200 in			Grid Convergence:			1.01 °		

Well	NBU 922-34F4CS, 2085 FSL 1026 FWL					
Well Position	+N/-S	0.00 ft	Northing:	14,526,642.84 usft	Latitude:	39.9910250
	+E/-W	0.00 ft	Easting:	2,079,830.07 usft	Longitude:	-109.4312330
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	4,989.00 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	BGGM2013	2/12/2014	10.79	65.79	51,982

<b>Design</b>	OH				
<b>Audit Notes:</b>					
<b>Version:</b>	1.0	<b>Phase:</b>	ACTUAL	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>	
	0.00	0.00	0.00	51.66	

<b>Survey Program</b>	<b>Date</b>	5/19/2014			
<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>	
9.00	2,493.00	Survey #1 SDI MWD SURFACE (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1	
2,579.00	9,208.00	Survey #2 SDI MWD PRODUCTION (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1	

<b>Survey</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Vertical Section (ft)</b>	<b>Dogleg Rate (°/100usft)</b>	<b>Build Rate (°/100usft)</b>	<b>Turn Rate (°/100usft)</b>	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
9.00	0.00	0.00	9.00	0.00	0.00	0.00	0.00	0.00	0.00	
179.00	0.53	21.77	179.00	0.73	0.29	0.68	0.31	0.31	0.00	
<b>FIRST SDI MWD SURFACE SURVEY</b>										
241.00	0.97	24.50	240.99	1.47	0.62	1.40	0.71	0.71	4.40	
334.00	1.85	358.22	333.96	3.69	0.90	2.99	1.15	0.95	-28.26	
428.00	3.34	357.16	427.86	7.94	0.71	5.49	1.59	1.59	-1.13	
522.00	3.87	359.80	521.68	13.85	0.57	9.04	0.59	0.56	2.81	
616.00	4.40	8.94	615.43	20.58	1.12	13.64	0.90	0.56	9.72	
708.00	4.82	22.71	707.14	27.64	3.16	19.62	1.28	0.46	14.97	



## Survey Report



<b>Company:</b>	US ROCKIES REGION PLANNING	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>TVD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Site:</b>	NBU 922-34L PAD	<b>MD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Well:</b>	NBU 922-34F4CS	<b>North Reference:</b>	True
<b>Wellbore:</b>	OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Denver Sales

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
803.00	5.80	34.61	801.73	35.27	7.42	27.70	1.55	1.03	12.53
898.00	7.21	43.39	896.12	43.55	14.25	38.19	1.81	1.48	9.24
992.00	8.79	45.15	989.20	52.90	23.39	51.17	1.70	1.68	1.87
1,084.00	10.46	48.14	1,079.91	63.44	34.59	66.49	1.89	1.82	3.25
1,176.00	12.58	49.49	1,170.05	75.52	48.43	84.84	2.32	2.30	1.47
1,271.00	14.42	52.89	1,262.42	89.38	65.73	107.00	2.11	1.94	3.58
1,365.00	16.36	54.29	1,353.05	104.17	85.82	131.93	2.10	2.06	1.49
1,460.00	18.20	54.03	1,443.75	120.69	108.69	160.12	1.94	1.94	-0.27
1,553.00	20.16	52.88	1,531.59	138.90	133.23	190.66	2.15	2.11	-1.24
1,647.00	21.40	50.50	1,619.47	159.58	159.38	224.00	1.60	1.32	-2.53
1,743.00	22.51	53.85	1,708.51	181.56	187.73	259.88	1.74	1.16	3.49
1,836.00	23.13	57.54	1,794.24	201.87	217.52	295.84	1.68	0.67	3.97
1,929.00	22.18	55.47	1,880.06	221.62	247.40	331.53	1.33	-1.02	-2.23
2,022.00	22.34	56.23	1,966.13	241.40	276.55	366.66	0.35	0.17	0.82
2,116.00	22.69	58.25	2,052.97	260.87	306.82	402.48	0.90	0.37	2.15
2,211.00	23.13	58.60	2,140.47	280.23	338.33	439.20	0.48	0.46	0.37
2,303.00	22.60	57.69	2,225.25	299.10	368.69	474.72	0.69	-0.58	-0.99
2,397.00	21.63	56.14	2,312.33	318.40	398.34	509.95	1.20	-1.03	-1.65
2,493.00	21.17	55.72	2,401.71	338.03	427.36	544.88	0.51	-0.48	-0.44
LAST SDI MWD SURFACE SURVEY									
2,579.00	19.72	54.53	2,482.29	355.19	452.01	574.87	1.75	-1.69	-1.38
FIRST SDI MWD PRODUCTION SURVEY									
2,674.00	19.79	53.47	2,571.70	374.07	477.99	606.95	0.38	0.07	-1.12
2,769.00	19.61	52.60	2,661.14	393.32	503.57	638.96	0.36	-0.19	-0.92
2,864.00	20.05	54.62	2,750.51	412.43	529.52	671.17	0.86	0.46	2.13
2,959.00	21.02	56.16	2,839.47	431.35	556.95	704.42	1.17	1.02	1.62
3,053.00	21.02	55.89	2,927.22	450.19	584.91	738.03	0.10	0.00	-0.29
3,148.00	23.11	54.15	3,015.25	470.67	614.13	773.66	2.30	2.20	-1.83
3,243.00	24.01	51.54	3,102.34	493.61	644.38	811.61	1.45	0.95	-2.75
3,338.00	21.55	46.18	3,189.93	517.72	672.11	848.32	3.39	-2.59	-5.64
3,433.00	21.02	48.82	3,278.45	541.02	697.52	882.70	1.15	-0.56	2.78
3,528.00	19.62	51.82	3,367.54	562.10	722.88	915.67	1.84	-1.47	3.16
3,623.00	18.03	52.42	3,457.45	580.92	747.07	946.32	1.69	-1.67	0.63
3,718.00	18.65	56.50	3,547.63	598.27	771.39	976.16	1.50	0.65	4.29
3,813.00	16.02	57.92	3,638.31	613.62	795.17	1,004.33	2.80	-2.77	1.49
3,908.00	17.78	59.68	3,729.20	627.91	818.80	1,031.73	1.93	1.85	1.85
4,003.00	20.89	55.54	3,818.84	644.82	845.29	1,063.00	3.58	3.27	-4.36
4,098.00	19.80	58.08	3,907.91	662.91	872.92	1,095.89	1.48	-1.15	2.67
4,193.00	20.31	57.34	3,997.15	680.32	900.45	1,128.28	0.60	0.54	-0.78
4,288.00	19.21	56.24	4,086.56	697.90	927.33	1,160.27	1.22	-1.16	-1.16
4,383.00	17.94	54.97	4,176.61	714.98	952.31	1,190.46	1.40	-1.34	-1.34
4,478.00	15.48	56.90	4,267.59	730.31	974.91	1,217.69	2.65	-2.59	2.03
4,573.00	16.62	60.86	4,358.89	743.85	997.40	1,243.73	1.66	1.20	4.17



## Survey Report



<b>Company:</b>	US ROCKIES REGION PLANNING	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>TVD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Site:</b>	NBU 922-34L PAD	<b>MD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Well:</b>	NBU 922-34F4CS	<b>North Reference:</b>	True
<b>Wellbore:</b>	OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Denver Sales

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,668.00	15.04	61.30	4,450.28	756.38	1,020.08	1,269.29	1.67	-1.66	0.46
4,763.00	13.37	62.18	4,542.37	767.43	1,040.61	1,292.25	1.77	-1.76	0.93
4,858.00	11.34	65.78	4,635.17	776.39	1,058.84	1,312.11	2.28	-2.14	3.79
4,953.00	9.58	67.71	4,728.59	783.22	1,074.67	1,328.76	1.89	-1.85	2.03
5,047.00	8.27	69.65	4,821.45	788.54	1,088.25	1,342.71	1.43	-1.39	2.06
5,142.00	6.77	66.75	4,915.63	793.12	1,099.80	1,354.62	1.63	-1.58	-3.05
5,237.00	4.57	62.35	5,010.16	797.09	1,108.30	1,363.74	2.36	-2.32	-4.63
5,332.00	3.43	67.19	5,104.93	799.95	1,114.27	1,370.20	1.25	-1.20	5.09
5,427.00	0.79	95.40	5,199.86	800.99	1,117.54	1,373.41	2.90	-2.78	29.69
5,522.00	0.62	132.66	5,294.85	800.58	1,118.57	1,373.96	0.50	-0.18	39.22
5,617.00	1.14	130.82	5,389.84	799.61	1,119.67	1,374.22	0.55	0.55	-1.94
5,712.00	1.06	154.11	5,484.82	798.21	1,120.77	1,374.21	0.47	-0.08	24.52
5,806.00	0.44	229.78	5,578.81	797.19	1,120.87	1,373.66	1.11	-0.66	80.50
5,902.00	0.70	216.95	5,674.81	796.48	1,120.24	1,372.73	0.30	0.27	-13.36
5,997.00	0.70	150.24	5,769.80	795.52	1,120.18	1,372.08	0.81	0.00	-70.22
6,092.00	0.70	165.62	5,864.80	794.45	1,120.61	1,371.76	0.20	0.00	16.19
6,186.00	0.44	147.96	5,958.79	793.59	1,120.94	1,371.48	0.33	-0.28	-18.79
6,281.00	0.35	151.03	6,053.79	793.03	1,121.28	1,371.40	0.10	-0.09	3.23
6,376.00	0.76	139.90	6,148.78	792.29	1,121.82	1,371.37	0.44	0.43	-11.72
6,466.00	1.32	311.87	6,238.78	792.52	1,121.43	1,371.21	2.31	0.62	191.08
6,566.00	0.91	323.01	6,338.76	793.93	1,120.10	1,371.03	0.46	-0.41	11.14
6,661.00	0.70	313.72	6,433.75	794.93	1,119.23	1,370.97	0.26	-0.22	-9.78
6,756.00	0.53	237.17	6,528.75	795.09	1,118.44	1,370.45	0.81	-0.18	-80.58
6,854.00	0.62	189.97	6,626.74	794.33	1,117.96	1,369.61	0.48	0.09	-48.16
6,946.00	0.26	103.83	6,718.74	793.79	1,118.08	1,369.36	0.71	-0.39	-93.63
7,041.00	0.83	12.03	6,813.74	794.41	1,118.43	1,370.02	0.92	0.60	-96.63
7,136.00	0.70	27.21	6,908.73	795.60	1,118.84	1,371.08	0.25	-0.14	15.98
7,231.00	1.58	339.21	7,003.71	797.34	1,118.64	1,372.01	1.29	0.93	-50.53
7,326.00	0.53	15.68	7,098.69	798.98	1,118.30	1,372.76	1.26	-1.11	38.39
7,421.00	0.44	17.97	7,193.69	799.75	1,118.53	1,373.42	0.10	-0.09	2.41
7,516.00	0.53	8.39	7,288.69	800.54	1,118.70	1,374.04	0.13	0.09	-10.08
7,611.00	0.44	106.30	7,383.68	800.87	1,119.12	1,374.57	0.77	-0.09	103.06
7,706.00	0.62	105.77	7,478.68	800.63	1,119.96	1,375.08	0.19	0.19	-0.56
7,801.00	0.79	121.77	7,573.67	800.14	1,121.01	1,375.61	0.27	0.18	16.84
7,895.00	0.62	104.21	7,667.67	799.68	1,122.06	1,376.14	0.29	-0.18	-18.68
7,991.00	0.94	74.19	7,763.66	799.76	1,123.32	1,377.18	0.53	0.33	-31.27
8,086.00	1.51	356.08	7,858.64	801.22	1,123.98	1,378.61	1.69	0.60	-82.22
8,181.00	1.23	352.65	7,953.61	803.48	1,123.77	1,379.84	0.31	-0.29	-3.61
8,276.00	0.88	340.79	8,048.60	805.18	1,123.40	1,380.60	0.43	-0.37	-12.48
8,372.00	0.79	320.66	8,144.59	806.39	1,122.74	1,380.83	0.32	-0.09	-20.97
8,466.00	1.02	4.54	8,238.58	807.73	1,122.39	1,381.39	0.75	0.24	46.68
8,562.00	0.64	353.39	8,334.57	809.11	1,122.40	1,382.26	0.43	-0.40	-11.61
8,657.00	0.35	329.01	8,429.56	809.89	1,122.19	1,382.57	0.37	-0.31	-25.66
8,751.00	0.24	107.68	8,523.56	810.07	1,122.23	1,382.72	0.59	-0.12	147.52



## Survey Report



<b>Company:</b>	US ROCKIES REGION PLANNING	<b>Local Co-ordinate Reference:</b>	Well NBU 922-34F4CS
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>TVD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Site:</b>	NBU 922-34L PAD	<b>MD Reference:</b>	GL 4989 & KB 18 @ 5007.00ft (SST 57)
<b>Well:</b>	NBU 922-34F4CS	<b>North Reference:</b>	True
<b>Wellbore:</b>	OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Denver Sales

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,847.00	0.53	110.96	8,619.56	809.85	1,122.83	1,383.06	0.30	0.30	3.42	
8,942.00	0.53	143.74	8,714.56	809.34	1,123.50	1,383.27	0.31	0.00	34.51	
9,037.00	0.88	138.99	8,809.55	808.44	1,124.24	1,383.28	0.37	0.37	-5.00	
9,133.00	1.93	142.95	8,905.52	806.59	1,125.70	1,383.28	1.10	1.09	4.13	
9,153.00	1.78	151.70	8,925.51	806.05	1,126.05	1,383.22	1.60	-0.75	43.75	
LAST SDI MWD PRODUCTION SURVEY										
9,208.00	1.78	151.70	8,980.48	804.55	1,126.86	1,382.92	0.00	0.00	0.00	
SDI PROJECTION TO TD										

Design Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
179.00	179.00	0.73	0.29	FIRST SDI MWD SURFACE SURVEY	
2,493.00	2,401.71	338.03	427.36	LAST SDI MWD SURFACE SURVEY	

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



## US ROCKIES REGION

**1 General****1.1 Customer Information**

Company	US ROCKIES REGION
Representative	
Address	

**1.2 Well/Wellbore Information**

Well	NBU 922-34F4CS RED	Wellbore No.	00
Well Name	NBU 922-34F4CS	Wellbore Name	NBU 922-34F4CS
Report no.	1	Report date	12/29/2014
Project	UTAH-UNTAH	Site	NBU 922-34L PAD
Rig Name/No.	ROCKY MOUNTAIN WELL SERVICE 1/1	Event	COMPLETION
Start date	7/9/2014	End date	1/14/2015
Spud date	2/21/2014	Active datum	RKB @5,007.00usft (above Mean Sea Level)
UWI	NW/SW/09/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0		

**1.3 General**

Contractor		Job method		Supervisor	
Perforated Assembly		Conveyed method			

**1.4 Initial Conditions**

Fluid type		Fluid density		Gross Interval	7,138.0 (usft)-9,110.0 (usft)	Start Date/Time	12/29/2014 12:00AM
Surface press.		Estimate res press		No. of intervals	51	End Date/Time	12/29/2014 12:00AM
TVD fluid top		Fluid head		Total shots	168	Net perforation interval	56.00 (usft)
Hydrostatic press.		Press. difference		Avg. shot density	3.00 (shot/ft)	Final surface pressure	
Balance Cond	NEUTRAL					Final press. date	

**1.5 Summary****2 Intervals****2.1 Perforated Interval**

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD top (usft)	MD base (usft)	Shot density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
12/29/2014 12:00AM	M E S A VERDE/			7,138.0	7,139.0	3.00		0.410 EXP/		3.125	120.00		19.00	PRODUCTION		

## US ROCKIES REGION

## 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD top (usft)	MD base (usft)	Shot density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
12/29/2014 12:00AM	M E S A VERDE/			7,157.0	7,158.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,190.0	7,192.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,232.0	7,234.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,238.0	7,240.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,294.0	7,295.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,334.0	7,335.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,343.0	7,344.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,349.0	7,350.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,369.0	7,370.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,393.0	7,394.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,426.0	7,427.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,438.0	7,439.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,568.0	7,569.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,588.0	7,589.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,633.0	7,634.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		

RECEIVED: Feb. 12, 2015

## US ROCKIES REGION

## 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD top (usft)	MD base (usft)	Shot density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
12/29/2014 12:00AM	M E S A VERDE/			7,658.0	7,659.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,676.0	7,677.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,721.0	7,722.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,749.0	7,750.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,822.0	7,823.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			7,993.0	7,994.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,054.0	8,055.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,071.0	8,072.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,136.0	8,137.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,219.0	8,220.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,232.0	8,233.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,258.0	8,259.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,278.0	8,279.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,330.0	8,331.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,362.0	8,363.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		

US ROCKIES REGION

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD top (usft)	MD base (usft)	Shot density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
12/29/2014 12:00AM	M E S A VERDE/			8,382.0	8,383.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,396.0	8,397.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,413.0	8,414.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,428.0	8,429.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,449.0	8,450.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,485.0	8,486.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,550.0	8,551.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,589.0	8,590.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,607.0	8,608.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,646.0	8,647.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,687.0	8,688.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,736.0	8,737.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,777.0	8,779.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,864.0	8,865.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/2014 12:00AM	M E S A VERDE/			8,917.0	8,918.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		




## US ROCKIES REGION

## 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD top (usft)	MD base (usft)	Shot density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
12/29/201 4 12:00AM	M E S A VERDE/			8,950.0	8,951.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/201 4 12:00AM	M E S A VERDE/			8,988.0	8,989.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/201 4 12:00AM	M E S A VERDE/			9,042.0	9,043.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/201 4 12:00AM	M E S A VERDE/			9,080.0	9,081.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		
12/29/201 4 12:00AM	M E S A VERDE/			9,108.0	9,110.0	3.00		0.410	EXP/	3.125	120.00		19.00	PRODUCTION		

## 3 Plots

## 3.1 Wellbore Schematic



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-34F4CS RED				Spud date: 2/21/2014					
Project: UTAH-UINTAH				Site: NBU 922-34L PAD				Rig name no.: ROCKY MOUNTAIN WELL SERVICE 1/1	
Event: COMPLETION				Start date: 7/9/2014				End date: 1/14/2015	
Active datum: RKB @5,007.00usft (above Mean Sea Level)				UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0					
Date	Time Start-End		Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
7/3/2014	-								
7/9/2014	8:00	- 9:30	1.50	SUBSPR	52	B	P		FILL SURFACE CSG. MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & SURFACE 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST -38 PSI. NO COMMUNICATION SURFACE HAS SLIGHT MIGRATION BLEED OFF PSI.  PRESSURE TEST 8 5/8 X 4 1/2 TO 512 PSI HELD FOR 5 MIN LOST -317 PSI, BLED PSI OFF, REINSTALLED POP OFF SWIFN 340 PSI ON SURFACE CASING FILLED SURFACE WITH 1 BBL H2O
12/23/2014	8:00	- 9:00	1.00	SUBSPR	52	B	P		FILL SURFACE CSG. MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & FRAC VALVES 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST -53 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI.
	9:00	- 10:00	1.00	SUBSPR	37	E	P		PERF STG 1)PU 3 1/8 EXP GUN, 19 GM, .40 HOLE SIZE. RIH PERFWELL, AS PER PERF DESIGN. POOH. SWIFW HSM-JSA
12/29/2014	6:30	- 6:45	0.25	FRAC	48		P		FRAC STG #1) WHP 1609 PSI, BRK 1854 PSI @ 4.1 BPM. ISIP 2609 PSI, FG. 0.73 ISIP 2661 PSI, FG. 0.73, NPI 52 PSI, X/O TO WL.
	6:45	- 17:30	10.75	FRAC	36	H	P		SET CBP & PERF STG #2 AS DESIGNED, X/O TO FRAC.  FRAC STG #2) WHP 964 PSI, BRK 2245 PSI @ 4.9 BPM. ISIP 1347 PSI, FG. 0.59 ISIP 2777 PSI, FG. 0.76, NPI 1430 PSI, X/O TO WL.  SET CBP & PERF STG #3 AS DESIGNED, X/O TO FRAC.  FRAC STG #3) WHP 1726 PSI, BRK 4670 PSI @ 4.8 BPM. ISIP 2224 PSI, FG. 0.69 ISIP 2601 PSI, FG. 0.74, NPI 377 PSI, X/O TO WL.
12/30/2014	6:30	- 6:45	0.25	FRAC	48		P		SET CBP & PERF STG #4 AS DESIGNED, SWI, SDFN. HSM-JSA

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: ROCKY MOUNTAIN WELL SERVICE  
1/1

Event: COMPLETION

Start date: 7/9/2014

End date: 1/14/2015

Active datum: RKB @5,007.00usft (above Mean Sea  
Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	6:45 - 17:30	10.75	FRAC	36	H	P		FRAC STG #4) WHP 1934 PSI, BRK 3513 PSI @ 4.7 BPM. ISIP 2523 PSI, FG. 4.7 ISIP 2647 PSI, FG. 0.76, NPI 124 PSI, X/O TO WL.  SET CBP & PERF STG #5 AS DESIGNED, X/O TO FRAC.  FRAC STG #5) WHP 703 PSI, BRK 2974 PSI @ 4.8 BPM. ISIP 1761 PSI, FG. 0.66 ISIP 2430 PSI, FG. 0.75, NPI 669 PSI, X/O TO WL.  SET CBP & PERF STG #6 AS DESIGNED, X/O TO FRAC.  FRAC STG #6) WHP 513 PSI, BRK 2505 PSI @ 4.7 BPM. ISIP 1330 PSI, FG. 0.64 ISIP 2351 PSI, FG. 0.75, NPI 1021 PSI, X/O TO WL.  SET CBP & PERF STG #7 AS DESIGNED, X/O TO FRAC.  FRAC STG #7) WHP 212 PSI, BRK 2395 PSI @ 4.7 BPM. ISIP 1518 PSI, FG. 0.64 ISIP 1926 PSI, FG. 0.7, NPI 408 PSI, X/O TO WL.  SET KILL PLUG.  RDMO WL & FRAC EQUIP.  TOTAL FLUID= 10242 BBLS TOTAL SAND= 216288 LBS
1/13/2015	7:00 - 7:15	0.25	DRLOUT	48		P		HSM, ROADING RIG
	7:15 - 11:30	4.25	DRLOUT	30	A	P		ROAD RIG FROM NBU 1022-5I3 PAD TO THE 922-34L PAD, MIRU ON THE RED WELL NBU 922-34F4CS, SPOT EQUIP, N/D WELL HEAD, N/U BOPS, R/U TBG EQUIP, MIRU SLAUGH PIPE WRANGLER.
	11:30 - 11:30	0.00	DRLOUT	31	I	P		P/U 3-7/8 BIT W/ POBS PKG, TALLEY AND P/U 224 JNTS 2-3/8 L-80 TBG, TAG @=7,080', P/U POWER SWIVEL, PREP TO DRILL OUT IN AM.
1/14/2015	7:00 - 7:15	0.25	DRLOUT	48		P		HSM, PRESSURE TESTING

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-34F4CS RED

Spud date: 2/21/2014

Project: UTAH-UINTAH

Site: NBU 922-34L PAD

Rig name no.: ROCKY MOUNTAIN WELL SERVICE  
1/1

Event: COMPLETION

Start date: 7/9/2014

End date: 1/14/2015

Active datum: RKB @5,007.00usft (above Mean Sea  
Level)

UWI: NW/SW/0/9/S/22/E/34/0/0/26/PM/S/2085/W/0/1026/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	7:15 - 17:00	9.75	DRLOUT	44	C	P		<p>SITP=0#, SICP=0# OPEN WELL PRESSURE TEST BOPS [NO LEAKS] BREAK CIRC W/ RIG PUMP DRILL THROUGH HALIBURTON PLUG @=7,080' IN 10 MIN W/ 200# PRESSURE INCREASE.</p> <p>PLUG #2] CONT. TO RIH, TAG @=7,237' [25' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=7,262' IN 6 MIN W/ #300 PRESSURE INCREASE.</p> <p>PLUG #3] CONT. TO RIH, TAG @=7,446' [30' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=7,476' IN 5 MIN W/ 600# PRESSURE INCREASE.</p> <p>PLUG #4] CONT. TO RIH, TAG @=7,808' [45' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=7,853' IN 10 MIN W/ 100# PRESSURE INCREASE.</p> <p>PLUG #5] CONT. TO RIH, TAG @=8,279' [30' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=8,309' IN 5 MIN W/ 750# PRESSURE INCREASE.</p> <p>PLUG #6] CONT. TO RIH, TAG @=8,491' [25' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=8,516' IN 6 MIN W/ 800# PRESSURE INCREASE.</p> <p>PLUG #7] CONT. TO RIH, TAG @=8,756' [45' FILL] C/O AND DRILL THROUGH HALIBURTON PLUG @=8,801' IN 8 MIN W/ 900# PRESSURE INCREASE. CONT. TO RIH C/O TO PBTD @=9,153' CIRC WELL, L/D 21 JNTS, P/U HANGER STRIPPED IN WELL, LANDED TBG W/ 268 JNTS 2-3/8 L-80 TBG @=8,521.88', R/D TBG EQUIP, R/D PIPE WRANGLER, N/D BOPS DROP BALL, N/U WELL HEAD, PUMP BIT OFF W/ 2,400# PRESSURE TURN OVER TO F/B CREW. RDMO</p> <p>KB 24.00 4-1/2 HANGER 2.20 268 JNTS 2-3/8 L-80 8,494.85 XN NIPPLE 2.20 EOT @= 8,521.88</p>